



BP Exploration Operating Company
Limited

Report



Schiehallion & Loyal Fields Phase 1 Decommissioning Comparative Assessment

December 12

BP Document No: DECOM-SCH-HS-CAS-BP-0080-B1



deeper understanding

Schiehallion & Loyal Fields Phase 1 Decommissioning Comparative Assessment

Project/Job Title: **Schiehallion & Loyal Fields Phase 1 Decommissioning Comparative Assessment**

Genesis Job Number: **J-60015/A**

BP Document No: DECOM-SCH-HS-CAS-BP-0080-A1

Prepared for:
BP Exploration Operating Company Limited

Prepared by Genesis:
6 Albyn Place, Aberdeen, AB10 1YH, UK
Tel: +44 (0)1224 615100 Fax: +44 (0)1224 615111
www.genesisoilandgas.com

| Rev | Date | Description | Issued by | Checked by | Approved by | Client Approval |
|-----------|-----------------|--|-----------------|------------------|------------------|-----------------|
| A1 | 18/12/12 | Issued for Review | J Wilson | S Ralston | S Ralston | |
| B1 | 20/12/12 | Client comments incorporated and Issued for Information | J Wilson | S Ralston | S Ralston | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Document No./File Name: J60015A-Y-RT-0001 B1: Schiehallion & Loyal Fields Phase 1 Decommissioning Comparative Assessment.docm

Contents

| | |
|--|----|
| ABBREVIATIONS | 8 |
| EXECUTIVE SUMMARY | 9 |
| Introduction | 9 |
| Background | 9 |
| Boundaries, Qualifications and Exclusions | 10 |
| Comparative Assessment..... | 10 |
| Results | 10 |
| 1.0 INTRODUCTION..... | 12 |
| 2.0 BACKGROUND..... | 16 |
| 2.1 General Infrastructure Description | 16 |
| 2.1.1 Flowlines..... | 18 |
| 2.1.2 Flowline Jumpers | 18 |
| 2.1.3 Risers and Dynamic umbilicals | 19 |
| 2.1.4 Fibre Optic Cable | 21 |
| 3.0 COMPARATIVE ASSESSMENT METHODOLOGY | 22 |
| 3.1 Assessment Criteria..... | 23 |
| 3.2 Comparative Impact..... | 24 |
| 4.0 COMPARATIVE ASSESSMENT CONCLUSIONS | 25 |
| 4.1 Oil Production System | 25 |
| 4.1.1 Oil Production Flowlines & FTAs..... | 25 |
| 4.1.2 Oil Production Manifold M1D | 25 |
| 4.1.3 Oil Production Risers & RETs | 25 |
| 4.1.4 Production Jumpers | 25 |
| 4.1.5 Summary Table of Comparative Assessment Workshop Outputs – Oil Production System..... | 27 |
| 4.2 Controls System | 29 |
| 4.2.1 Control Distribution Assemblies (CDAs)..... | 29 |
| 4.2.2 Fly to Place Connectors (FTPs) | 29 |
| 4.2.3 Static Umbilicals & UETs | 29 |
| 4.2.4 Dynamic Umbilicals & DUTAs | 29 |
| 4.2.5 Summary Table of Comparative Assessment Workshop Outputs – Control System31 | |
| 4.3 Gas Systems | 32 |
| 4.4 Water Injection System | 32 |
| 4.4.1 WI Risers & RET | 32 |

| | | |
|-------|---|----|
| 4.4.2 | WI Jumpers..... | 33 |
| 4.4.3 | Summary Table of Comparative Assessment Workshop Outputs – Water Injection System | 34 |
| 4.5 | Other Structures | 35 |
| 4.5.1 | Grout Bags..... | 35 |
| 4.5.2 | Mattresses | 35 |
| 4.5.3 | Produced Water Re-injection (PWRI) pump skids..... | 36 |
| 4.5.4 | Anode Skids..... | 36 |
| 4.5.5 | Summary Table of Comparative Assessment Workshop Outputs – Other Structures | 37 |
| 5.0 | CONCLUSIONS AND RECOMMENDATIONS..... | 39 |
| 6.0 | APPENDIX A – OPTIONS ASSESSMENT MATRICES..... | 40 |
| 6.1 | OIL PRODUCTION SYTEMS | 40 |
| 6.1.1 | Technical Risk | 40 |
| 6.1.2 | Safety | 41 |
| 6.1.3 | Environmental Impact | 42 |
| 6.1.4 | Societal Impact | 43 |
| 6.1.5 | Economic..... | 43 |
| 6.2 | CONTROL SYSTEMS | 44 |
| 6.2.1 | Technical Risk | 44 |
| 6.2.2 | Safety | 45 |
| 6.2.3 | Environmental Impact | 46 |
| 6.2.4 | Societal Impact | 47 |
| 6.2.5 | Economic..... | 47 |
| 6.3 | WATER INJECTION SYSTEMS | 48 |
| 6.3.1 | Technical Risk | 48 |
| 6.3.2 | Safety | 48 |
| 6.3.3 | Environmental Impact | 49 |
| 6.3.4 | Societal Impact | 50 |
| 6.3.5 | Economic..... | 50 |
| 6.4 | OTHER STRUCTURES..... | 51 |
| 6.4.1 | Technical Risk | 51 |
| 6.4.2 | Safety | 52 |
| 6.4.3 | Environmental Impact | 53 |
| 6.4.4 | Societal Impact | 55 |
| 6.4.5 | Economic..... | 56 |

| | | |
|-------|---|----|
| 7.0 | APPENDIX B – FIELD INFRASTRUCTURE DETAILS..... | 57 |
| 7.1 | OIL PRODUCTION STRUCTURES - Returned to Service at Quad 204 Start-Up 57 | |
| 7.1.1 | OIL Production Jumpers | 57 |
| 7.2 | OIL Flowline Jumpers - to be suspended, but not recovered within Phase 1 Decomm window (recovery post 2015)..... | 57 |
| 7.3 | CONTROL STRUCTURES - Returning to Service after Quad 204 Start-Up | 58 |
| 7.3.1 | CONTROL Fly to Place Connector (FTP) | 58 |
| 7.3.2 | Controls Distribution Assembly (CDA):..... | 59 |
| 7.4 | GAS SYSTEM STRUCTURES Returning to Service after Quad 204 Start-Up... | 59 |
| 7.4.1 | GAS Flowlines | 59 |
| 7.4.2 | GAS Flowline Termination Assemblies (FTAs)..... | 60 |
| 7.4.3 | Gas Jumpers | 60 |
| 7.4.4 | GAS Manifolds..... | 61 |
| 7.4.5 | GAS Pipeline End Manifold..... | 61 |
| 7.5 | WATER INJECTION STRUCTURES - Returning to Service after Quad 204 Start-Up Up | 61 |
| 7.5.1 | WI Flowlines | 61 |
| 7.5.2 | WI Flowline Termination Assembly (FTA) | 62 |
| 7.5.3 | WI Jumper | 62 |
| 7.5.4 | WI Manifold..... | 64 |
| 7.6 | WI Flowline Jumper to be suspended, but not recovered within Phase 1 Decomm window (recovery post 2015)..... | 64 |
| 7.7 | OIL PRODUCTION STRUCTURES – LONG TERM SUSPENSION..... | 64 |
| 7.7.1 | OIL Flowlines | 64 |
| 7.7.2 | OIL Flowline Termination Assemblies (FTA's)..... | 65 |
| 7.7.3 | OIL Manifold | 65 |
| 7.8 | CONTROL STRUCTURES – LONG TERM SUSPENSION..... | 66 |
| 7.8.1 | CONTROL Static Umbilical | 66 |
| 7.8.2 | CONTROL Umbilical End Termination (UET)..... | 66 |
| 7.8.3 | CONTROLS Fly to Place connector (FTP) | 67 |
| 7.9 | GAS SYSTEM STRUCTURES – LONG TERM SUSPENSION | 67 |
| 7.9.1 | GAS Flowlines | 67 |
| 7.9.2 | GAS Flowline Termination Assemblies (FTAs)..... | 67 |
| 7.9.3 | Gas Jumper | 67 |
| 7.10 | WATER INJECTION SYSTEM STRUCTURES – LONG TERM SUSPENSION | 67 |

| | |
|--|----|
| 7.11 OIL PRODUCTION SYSTEM STRUCTURES – RECOVER AND RECYCLE | 68 |
| 7.11.1 Oil Risers | 68 |
| 7.11.2 OIL Riser End Terminations (RET) | 68 |
| 7.11.3 OIL Production Jumpers | 68 |
| 7.12 CONTROL SYSTEM STRUCTURES – RECOVER AND RECYCLE | 70 |
| 7.12.1 CONTROL Dynamic Umbilical | 70 |
| 7.12.2 CONTROL Dynamic Umbilical Termination Assembly (DUTA) | 70 |
| 7.12.3 CONTROL Fly to Place connector (FTP) | 70 |
| 7.12.4 Controls Distribution Assembly (CDA):..... | 72 |
| 7.13 GAS SYSTEM STRUCTURES – RECOVER AND RECYCLE | 72 |
| 7.13.1 Gas Risers | 72 |
| 7.14 WATER INJECTION SYSTEM STRUCTURES – RECOVER AND RECYCLE .. | 73 |
| 7.14.1 WI Riser | 73 |
| 7.14.2 WI Riser End Termination (RET)..... | 73 |
| 7.14.3 WI Jumper | 73 |

Figures & Tables

Figures

| | |
|---|----|
| Figure 1.1 Location of Schiehallion and Loyal Fields..... | 12 |
| Figure 1.2 Schematic of Existing Schiehallion and Loyal Field layout – By System..... | 15 |
| Figure 2.1 Schematic of Existing Schiehallion and Loyal Field layout – By Fate..... | 17 |

Tables

| | |
|---|----|
| Table 1-1 Existing Production and Water Injection Wells by Drill Centre | 13 |
| Table 1-2 Existing Flowlines, Umbilicals, Risers, Manifolds and Jumpers | 13 |
| Table 2-1 Existing Flowlines by Drill Centre | 18 |
| Table 2-2 Existing Flowline Jumpers by Drill Centre and Service | 19 |
| Table 2-3 Existing Risers and dynamic umbilicals to be recovered | 20 |
| Table 3.1 Team Composition | 22 |
| Table 3.2 Assessment criteria and aspects for options assessment..... | 23 |
| Table 3.3 Comparative impact | 24 |
| Table 4-1 Summary of Oil Production System Comparative Assessment..... | 27 |
| Table 4-2 Summary of Oil Production System Comparative Assessment (continued) | 28 |
| Table 4-3 Summary of Control System Comparative Assessment | 31 |
| Table 4-4 Summary of Water Injection System Comparative Assessment | 34 |
| Table 4-5 Summary of Other Structures Comparative Assessment..... | 37 |
| Table 4-6 Summary of Other Structures Comparative Assessment (continued) | 38 |

ABBREVIATIONS

| | |
|--------------|---|
| CA | Comparative Assessment |
| CDA | Controls Distribution Assembly |
| COP | Cessation of Production |
| CRA | Corrosion Resistant Alloy |
| DECC | Department of Energy and Climate Change |
| DP | Decision Paper |
| DUTA | Dynamic Umbilical Termination Assembly |
| EDC | Environmental Debris Cap |
| EoFL | End of Field Life |
| FPSO | Floating Production Storage and Offloading vessel |
| FTA | Flowline Termination Assembly |
| FTP | Fly to Place Connector |
| IE | Independent Expert |
| LTC | Lower Tether Clamp |
| km | Kilometre |
| m | meter |
| ML | Multi- Lateral |
| NGO | Non Government Organisation |
| NWAD | North West Area Development |
| PLEM | Pipeline End Manifold |
| PWRI | Produced Water Re-Injection |
| RET | Riser End Termination |
| ROVDB | ROV Deployable Blind |
| TOR | Terms of Reference |
| UET | Umbilical End Termination |
| UKCS | United Kingdom Continental Shelf |
| UTC | Upper Tether Clamp |
| VLS | Vertical Lay System |
| WI | Water Injection |

EXECUTIVE SUMMARY

Introduction

This report presents the findings of a Comparative Assessment (CA) of options for Schiehallion & Loyal Fields Phase 1 decommissioning of pipelines, associated apparatus and other subsea infrastructure.

The Schiehallion & Loyal Phase 1 Decommissioning Programmes cover the decommissioning of the existing infrastructure that becomes redundant as part of the Quad 204 Project (Schiehallion FPSO Replacement).

The focus of this CA has been on all subsea infrastructures associated apparatus and other subsea infrastructure including:

- Risers
- Riser End Terminations (RETs)
- Dynamic Umbilicals
- Dynamic Umbilical Termination Assemblies (DUTAs)
- Flowlines
- Flowline Termination Assemblies (FTAs)
- Jumpers
- Static Umbilicals
- Umbilical End Terminations (UETs)
- Fly-to-Place connectors (FTPs)
- Controls Distribution Assemblies (CDAs)
- Manifolds
- Pipeline End Manifold (PLEM)
- Other Structures (redundant structures – PWRI pumping skids, Anode skids)
- Pipeline protection and stabilisation (Grout bags and mattresses)

Background

Most of the development work for Schiehallion & Loyal Fields Phase 1 Decommissioning Programmes completed to date has been carried out under the Quad 204 Project (FPSO Replacement) and the associated Schiehallion & Loyal Fields Suspension Project.

Both of these projects have carried out an option selection process and have determined the strategy for the various existing elements of Schiehallion and Loyal infrastructure and decided whether existing facilities are to be;

- Suspended short term and returned to service for Quad 204 duty;
- Suspended Long term, cleaned, preserved, left insitu and monitored until final decommissioning at Quad 204 end of field life (EoFL);
- Decommissioned and recovered during Schiehallion and Loyal Phase 1 Decommissioning programmes.

The CA has been completed on these options, but has also reviewed an additional option of;

- Insitu decommissioning of equipment on the seabed during Schiehallion and Loyal Phase 1 Decommissioning programmes.

Boundaries, Qualifications and Exclusions

The boundaries of this CA include all subsea infrastructures from the point where the risers disconnect from the FPSO to the final connections on the subsea trees at each of the drill centres.

Facilities that are to be suspended and not brought back into service as part of Quad 204 project therefore remain redundant and facilities that are to be decommissioned as part of Schiehallion & Loyal Fields Phase 1 Decommissioning Programmes have been considered in this CA.

Where a Quad 204 Project decision has already been reached to retain and re-use existing equipment for future Quad 204 Project duty, this decision has been accepted by the CA process. The CA has not attempted to judge the efficacy of the decision to re-use nor to assess the fitness for purpose of the facilities being retained for its new duty.

The CA process has not attempted to predict recoverability of the facilities to be re-used for Quad 204 duty at EoFL. This will be assessed at a future date as part of the Quad 204 EoFL Decommissioning Programme(s) development and its specific CA process.

The Schiehallion & Loyal Fields Phase 1 Decommissioning Programmes cover Schiehallion & Loyal Field Suspension activity from existing FPSO sail-away and until the new FPSO comes on station. Any subsea infrastructure decommissioning activity anticipated to be out with this period has not been considered in the CA.

FPSO modifications and the preparation of the FPSO for disconnect (flushing and purging and safe isolations of systems), the subsequent disconnection, FPSO towing and yard activities have not been assessed as part of the CA.

The FPSO mooring systems are considered as part of the FPSO installation and therefore decommissioning plans for this equipment have not been assessed as part of the CA.

The field preparation strategy and wells shut-in i.e. preparation of the Schiehallion and Loyal reservoir for future Quad 204 start-up e.g. continued WI for a period after Cessation of Production (COP) and wells isolation strategy will also not be considered during this CA.

Comparative Assessment

A CA Workshop was held on 11 December 2012 at which the options for treatment of the pipelines and their associated equipment were assessed against technical risk, safety, environmental, societal and economic criteria.

The Workshop participants have been drawn from the engineers and other specialists working on the Quad 204 and Schiehallion Field Suspension projects. GENESIS has introduced independent expert (IE) engineers from Subsea, Technical Safety and Risk, Environmental and Facilities.

During the Workshop options were grouped by subsea system and sub grouped by type of structure and then assessed by a qualitative traffic light approach, recognising that the overall project objective is redevelopment of the fields.

Results

Summary tables of the comparative assessment results by system are provided in Section 4.0

Generally the CA has concluded that re-use of existing infrastructure for Quad 204 duty where technically feasible is the best option. This is the case for the majority of infrastructure and is already the strategy being adopted by the Quad 204 project.

Where existing infrastructure is either not compatible with the Quad 204 duty or where there are concerns over integrity of the equipment for continued long term operation the CA has concluded that to suspend long term and preserve to Quad 204 EoFL is the best option. Suspend long term is favoured over the other remaining options during Phase 1 decommissioning due to potential technical and safety risks imposed on adjacent infrastructure planned to be re-used. i.e. potential damage when working close to or over retained equipment. There are also potentially large environmental impacts, if adjacent live infrastructure (wells) was damaged during execution activities.

By suspending and preserving the redundant equipment, the options to both decommission insitu or recover and recycle remain available at Quad 204 EoFL.

Examples where long term suspension are recommended is the oil production rigid flowlines, static umbilicals and some larger structures.

There are some instances where equipment is to be replaced as part of the Quad 204 project and where the redundant equipment location will impede installation of the replacement equipment. In such cases recovery and recycle of the redundant equipment is the only technically feasible option to clear the area for the new equipment. Examples where recovery and recycle are the only technically feasible option are the risers and associated riser end termination assemblies (RETs) and the dynamic umbilicals and associated dynamic umbilical termination assembly (DUTA). Risks in recovery of these items during Phase 1 decommissioning is less than other infrastructure as they are located local to the FPSO site and away from the drill centres and live equipment.

The CA concluded that decommissioning insitu during Phase 1 decommissioning was not a favoured option for any of the redundant equipment as it was either


- not technically feasible
- created higher technical and safety risk to adjacent live infrastructure
- removed contingency for future use of the equipment
- removed future decommissioning options at Quad 204 EoFL

1.0 INTRODUCTION

GENESIS was commissioned by BP plc (BP) to facilitate and provide Independent Expert (IE) participation in a CA Workshop to review the options considered for Schiehallion & Loyal Fields Phase 1 Decommissioning Project.

Schiehallion & Loyal fields lie approximately 150 km west of Shetland Islands in Quadrant 204 and 205 of the UKCS.

Figure1.1 Location of Schiehallion and Loyal Fields



The Schiehallion area development lies in a water depth ranging from about 350m to 500m and comprises the following drill centres;

- Central - Production & WI wells;
- West - Production & WI wells;
- North West Area Development(NWAD) - Production & WI wells;
- Loyal - Production & WI wells;

- North – WI well only.
- At the An' Teallach gas disposal structure (near to the west drill centre)

In total there are currently 53 active wells (52 trees) in the field; 26 production wells (25 trees) and 27 water injection. All wells will be shut-in during Field Suspension. All trees are to be retained and re-used at re-commissioning of the new FPSO.

There is also 1 gas disposal well which is currently suspended.

The wells are located at the five drill centres as shown in Table 1-1.

Table 1-1 Existing Production and Water Injection Wells by Drill Centre

| Drill centre | No. of production wells | No. of water injection wells |
|---|-------------------------|------------------------------|
| Central | 14 | 9 |
| West | 6 | 9 |
| North West | 1 (ML)* | 2 |
| North | 0 | 3 |
| Loyal | 4 | 4 |
| *Multi-lateral; 2 wells originating from a single multi-lateral well. | | |

The Schiehallion Field is scheduled to be further developed and thereafter known as Quad 204. An additional 25 wells are planned (Production and WI) located in the existing drill centres, with five (5) additional/ new flowlines and ten (10) replacement flowlines scheduled to be installed in 2014.

The existing FPSO is scheduled to be removed and towed away in 2013 and replaced in 2015 by a newly built and upgraded FPSO. The new FPSO shall utilise the existing subsea infrastructure when practicably possible.

Figure 1.2 below, shows the existing field layout.

The main items of the existing subsea infrastructure connecting the drill centres to the FPSO is summarised in Table 1.2.

Table 1-2 Existing Flowlines, Umbilicals, Risers, Manifolds and Jumpers

| Infrastructure | Quantity |
|---|----------|
| Production flowlines | 10 |
| Water injection flowlines | 6 |
| Gas lift flowlines | 4 |
| Gas import/export flowlines | 3 |
| Gas disposal flowline (currently unused) | 1 |
| Dynamic umbilicals | 3 |
| Static umbilicals | 10 |
| Risers | 15 |
| Manifolds | 23 |
| Flowline Jumpers | 100* |
| *31 of the 100 jumpers are a bundle of 3 jumpers (2 production and 1 gas) | |

Additional structures include Dynamic Umbilical Termination Assemblies (DUTAs); Fly-to-Place connectors (FTPs), Controls Distribution Assemblies (CDAs), Umbilical End Terminations (UETs), Riser End Terminations (RETs), Flowline Termination Assemblies (FTAs) and a Pipeline End Manifold (PLEM)


Before the existing FPSO is disconnected to be towed away, the field will be fully suspended with the aim of maintaining the existing subsea infrastructure in a preserved and safe condition, this is known as the Field Suspension phase.

The plans for the subsea infrastructure during Field Suspension vary:

- Some facilities will be suspended and preserved short term and then returned to service at the same location when the new FPSO is on station e.g. all gas lift and water injection flowlines and the majority of the flowline jumpers;
- Some facilities will be relocated before being returned to service when the new FPSO is on station e.g. predominantly the FTPs fall into this category;
- Some facilities will be isolated, flushed, cleaned, capped and dosed with preservation fluid, but will be left suspended long term on the seabed - until Quad 204 End of Field Life (EoFL) circa 2035 e.g. the production flowlines and associated FTAs and the static umbilicals;
- Some facilities will be recovered as part of the Field Suspension Project e.g. the risers and some of the flowline jumpers;
- Some facilities will be removed over a number of years as part of the Field Installation Project. However this CA has not assessed any future removals that may occur out with the period of Phase 1 decommissioning.

Figure 1.2 Schematic of Existing Schiehallion and Loyal Field layout – By System

Field Suspension Project 2013



- Existing Gas
- Existing Umbilical
- Existing Production
- Existing Water
- Proposed COCOT FTP
- Fibre Optic Cable

Produced by J.P. Kenny Caledonia Ltd
 Date /09-07-12
 O:\Graphics\drwg no. FLD189

| REV | DATE | BY | CHK | ENG | PM | CLIENT |
|-----|------------|----|-----|-----|----|--------|
| A2 | 05/07/2012 | AW | RC | KI | SG | |
| A1 | 23/04/2012 | AW | TH | JS | SG | |



| | |
|---------|--------------------------------------|
| PROJECT | QUAD 204 |
| CLIENT | BP Exploration Operating Company Ltd |



| | |
|-------|-------------------------------|
| TITLE | Field Suspension Project 2013 |
|-------|-------------------------------|

| | | | | | |
|----------------|----|------------|----------------------|-------|-----|
| OFFICE | 06 | PROJECT NO | 2960.06 | SCALE | N/A |
| DRAWING NUMBER | | | QD-JP-PL-GAS-0046-01 | REV. | A2 |



2.0 BACKGROUND

This section identifies and quantifies the different subsea facilities covered by this CA and expands upon which options have already been proposed by the Field Suspension Project.

2.1 General Infrastructure Description

An itemised list of subsea components together with the Quad 204 project proposals for each component is provided in **Appendix B** of this report.

This list is grouped first by System:

- Oil Production;
- Gas Systems;
- Water Injection;
- Controls;
- Other Structures


The list is then grouped by structure type

- Risers
- Riser End Terminations (RETs)
- Dynamic Umbilicals
- Dynamic Umbilical Termination Assemblies (DUTAs)
- Flowlines
- Flowline Termination Assemblies (FTAs)
- Jumpers
- Static Umbilicals
- Umbilical End Terminations (UETs)
- Fly-to-Place connectors (FTPs)
- Controls Distribution Assemblies (CDAs)
- Manifolds
- Other Structures and associated apparatus

Figure 2.1 is a schematic of the existing infrastructure colour coded by current project fate for each structure.

Figure 2.1 Schematic of Existing Schiehallion and Loyal Field layout – By Fate

Field Suspension Project 2013



Produced by J P Kenny Caledonia Ltd
Date /
O:\Graphics\rdg no. FLD

GAS DISPOSAL SITE

| REV | DATE | BY | CHK | ENG | PM | CLIENT |
|-----|------|----|-----|-----|----|--------|
| | | | | | | |
| | | | | | | |
| | | | | | | |



| | |
|---------|---|
| PROJECT | QUAD 204 |
| CLIENT | BP Exploration Operating Company Ltd |



| | |
|-------|--|
| TITLE | Fate of Subsea Lines at Field Restart (2016) |
|-------|--|

| | | |
|--------|----------------|-------|
| OFFICE | PROJECT NO | SCALE |
| | | N/A |
| | DRAWING NUMBER | REV. |
| | | |

2.1.1 Flowlines

In total there are 22 rigid flowlines at Schiehallion. Table 1.3 describes the flowline configuration by drill centre and provides overall length of the flowlines.

Table 2-1 Existing Flowlines by Drill Centre

| Drill Centre | Production | Water Injection | Gas System |
|-----------------------------|-----------------|-----------------|----------------|
| Central (overall length) | 4 (10,213 m) | 1 (2,548 m) | 2 (2,872 m) |
| West (overall length) | 3 (8,196 m) | 2 (6,347 m) | 1 (3,270 m) |
| NWAD (overall length) | 1 (2,280 m) | 1 (3,141 m) | 1 (3,041 m) |
| North (overall length) | 0 n/a | 1 (2,271 m) | 0 n/a |
| Loyal (overall length) | 2 (11,550 m) | 1 (4, 883 m) | 1 (5,979 m) |

There is also one (1) Gas disposal flowline which is 6613 m long to the An' Teallach gas disposal structure; near to the west drill centre this flowline is already suspended.

The Quad 204 project has decided to re-use the 6 existing Water Injection flowlines and the 7 existing Gas flowlines (4 Gas lift and 3 gas import/ export) for Quad 204 duty, but have integrity concerns with the 10 oil production flowlines.

These flowlines when installed had a design life of 20 years. The majority of the flowlines started operation in July 1998 giving a target life to 2018. The most recent flowlines at the West development and NWAD started operation in 2005 and 2006 giving a target life of 2025/2026. Inspection records from similar flowlines with similar duty have revealed earlier than anticipated deterioration due to corrosion.

The Quad 204 project has therefore decided to replace all 10 oil production flowlines.

2.1.2 Flowline Jumpers

In total there are 162 flowline jumpers across the field

- 39 WI jumpers
- 46 Gas jumpers
- 1 Gas disposal jumper (currently suspended)
- 76 Oil production jumpers

Whilst all 39 water injection jumpers are dedicated / single jumpers, this is not the case for all of the production and gas lift jumpers. A large proportion of these have been installed as jumper bundles (separate lines loosely bundled and tied together). These bundles are configured with two 6" production lines and one 2" gas lift line in each bundle. There are 31 bundled jumpers in the field accounting for 62 production jumpers and 31 gas jumpers.

There are a further 14 single production jumpers and 15 single gas lift jumpers and one single gas disposal jumper. The gas disposal jumper is currently in a suspended state.

Table 1.4 describes the flowline jumpers' configuration by drill centre and provides overall length of the jumpers.

Table 2-2 Existing Flowline Jumpers by Drill Centre and Service

| Drill Centre | Production | | Gas Lift | | Water Injection Single |
|--------------|------------|---------------|----------|---------------|---------------------------|
| | Single | Within bundle | Single | Within bundle | |
| Central | 4 | 36 | 7 | 18 | 10 |
| | (337 m) | (1,544 m) | (814 m) | (777 m) | (408 m) |
| West | 5 | 14 | 0 | 7 | 14 |
| | (832 m) | (534 m) | n/a | (267 m) | (869 m) |
| North West | 3 | 2 | 2 | 1 | 4 |
| | (217 m) | (228 m) | (344 m) | (114 m) | (388 m) |
| North | 0 | 0 | 0 | 0 | 6 |
| | n/a | n/a | n/a | n/a | (278 m) |
| Loyal | 2 | 10 | 2 | 5 | 5 |
| | (99 m) | (446 m) | (201 m) | (223 m) | (250 m) |

Quad 204 project have decided to re-use 36 of the 39 WI jumpers for Quad 204 duty, but 3 jumpers are to be replaced as they are not the correct length for the revised field configuration.

Quad 204 project have decided to re-use all 15 single gas jumpers, but 6 jumpers that are bundled with production jumpers are to be replaced as they are not the correct length for the revised field configuration.

It is intended to retain the 1 gas disposal jumper in a suspended state longer term as a contingency in case a gas disposal route is required in the future.

Twelve (12) of the 14 single oil production jumpers are not the correct length for the revised field configuration and are to be replaced. Quad 204 have decided to use 25 of the 31 existing bundled jumpers; however 6 are to be replaced as they are not the correct length for the revised field configuration.

2.1.3 Risers and Dynamic umbilicals

There are a total of 15 risers (10 Production, 3 Water Injection & 2 Gas) and 3 dynamic umbilicals in the field.

There were 4 criteria assessed by the Quad 204 project to determine potential for re-use of the existing risers;

- Existing riser integrity;
- Existing riser compatibility with new FPSO Turret requirements, practicality of modification to riser to suit new arrangement;
- Practicalities of riser storage (wet or dry);
- Optimisation of abandonment schedule, dependent on disconnection methods and storage option selected;

The conclusion at the Define Stage of the Quad 204 project was that all 15 existing risers will be replaced with new risers. At least 6 of the existing redundant risers will be assessed for potential re-use as spares once back onshore. The remaining risers will be managed under BP's Waste Management Plan and Waste Hierarchy QD-BP-EV-PLN-002.

Two out of the three existing dynamic umbilicals currently have significant faults and would be due for replacement under the current operating regime if the FPSO was not planned to go off station in the near future. The ability to seal and repack the 3rd umbilical (SECU D3) against water ingress if wet stored on the seabed for future re-use was identified as a major technical risk and subsequent uncertainty of failure of the umbilical due to water ingress

manifesting itself only on Quad 204 start-up would have major commercial implications, by delaying start-up. Recovery of the 3rd umbilical for dry storage and re-use has also been considered. However due to existing issues with the methanol core within the existing umbilical Quad 204 project has decided to replace the umbilical with a new umbilical. The existing SECU D3 umbilical will be retained onshore as an emergency spare.

A total of 15 risers and 3 dynamic umbilicals are to be replaced. (Table 1-5).

Table 2-3 Existing Risers and dynamic umbilicals to be recovered

| Line type | Number | Minimum length (m) | Maximum length (m) | Total length (m) |
|--|--------|--------------------|--------------------|------------------|
| Production riser | 10 | 705 | 777 | 7,408 |
| Water injection riser | 3 | 697 | 777 | 2,199 |
| Gas lift riser | 1 | 749 | 749 | 749 |
| Gas import / export riser | 1 | 721 | 721 | 721 |
| Dynamic umbilical (includes 1 suspended) | 3 | 725 | 1,924 | 3,389 |

The risers and umbilicals are fixed to the seabed at two points. Two clamps are located along each riser / dynamic umbilical – an upper tether clamp (UTC) and a lower tether clamp (LTC).

The UTC is fixed to a swivel mechanism which allows for movement of the riser / dynamic umbilical. The UTC swivel mechanism is attached to the seabed by piles.

The LTC is positioned on the risers / dynamic umbilicals just before they connect to the flowlines / static umbilicals and serve to reduce the load where the dynamic structures connect to the static lines. The LTC is attached to the seabed via a suction anchor.

When recovering the risers / dynamic umbilicals the ends that were originally attached to the FPSO - will be winched onboard the vessel and the remainder will be gathered in by reeling the lines back on to a carousel. In order to carry this out the UTC will be attached to the seabed with a temporary clump weight.

Then the UTC is subsequently disconnected from the piled swivel mechanism. The LTC will be disconnected from the suction anchor allowing the risers/ dynamic umbilicals to be reeled in. The temporary clump weight attached to the UTC will remain attached to the risers / umbilicals as they are being reeled in.

None of the suction anchors or piles currently serving to anchor the risers / dynamic umbilicals is to be reused for Quad 204 duty. It is therefore proposed to recover the swivel mechanisms and suction anchors.

Two options were considered for decommissioning the piles associated with the UTC swivel mechanism:

- Option 1 - The piles will be driven about a metre below the surface of the seabed
- Option 2 - The piles will be cut about a metre below the seabed and the upper part will be recovered. This option will involve removing the seabed substrate around the top of the pile either by flushing or dredging.

Option 1 is currently the preferred project option.

Following recovery, the fate of the risers, dynamic umbilicals and anchoring structures will be managed under BPs Waste Management Plan and Waste Hierarchy QD-BP-EV-PLN-002.

2.1.4 Fibre Optic Cable

There is an existing fibre optic cable that connects the FPSO to the Faroes Fibre Optic System via dynamic umbilical W-2U. This cable will be re-used to connect the new FPSO via a new dynamic umbilical. The cable will be disconnected at the FPSO coiled and stored in a basket on the seabed for reconnection to the Quad 204 FPSO when it comes on station. This item has not been part of the CA.

3.0 COMPARATIVE ASSESSMENT METHODOLOGY

GENESIS were engaged to facilitate and provide Independent Expert (IE) participation in a CA Workshop to review the options considered for Schiehallion & Loyal Fields Phase 1 Decommissioning Project - specifically for the subsea infrastructure described in Section 2.0.

The methodology for the CA is based on the DECC Guidance Notes on Decommissioning of Offshore Oil and Gas Installations and Pipelines under the Petroleum Act 1998 (DECC, 2011). These Guidance Notes describe the assessment required for Annex 2 OSPAR derogation candidates. Annex 2 is not directly applicable to the decommissioning of pipelines; however, these requirements have been adapted as a result of DECC's Guidance Notes stating that Decommissioning Programmes for pipelines should also include a CA.

A CA Workshop was therefore convened on 11th December 2012.

The Workshop participants have been drawn from the engineers and other specialists working on the Quad 204 and Schiehallion Field Suspension projects. GENESIS has introduced IE engineers from Subsea, Technical Safety and Risk, Environmental and Facilities. The participants at the Workshop are listed in Table 3-1 below

Table 3.1 Team Composition

| Name | Designation | Project or Independent |
|---------------------------|---|------------------------|
| John Wilson | GENESIS Facilities IE / Workshop Chairman | Independent |
| Martha O'Sullivan | GENESIS Environmental IE / Scribe | Independent |
| Jim Blacklaws | BP SPM Decommissioning Team | Project |
| Douglas Johnston | BP Decommissioning - Subsea Engineer | Project |
| Calum Myles (Part – Time) | BP Subsea System Lead Engineer | Project |
| Dave Mayers | BP Quad 204 Subsea Installation Engineer | Project |
| Lindsay Baxter | BP Pipelines Installation and Equipment Disposal Engineer | Project |
| Gemma Lang | GENESIS Subsea IE | Independent |
| Ged Adams | BP HSSE Lead | Project |
| Mark Haines | BP Field Suspension HSSE Lead | Project |
| Susan Stephens | GENESIS Tech Safety and Risk IE | Independent |
| Tim Hollis | BP Environmental Lead | Project |
| Andrew Foster | BP Quad 204 Environmental Lead | Project |
| Sean Hayes | GENESIS Environmental Engineer | Project |
| Keith Mayo | BP Decommissioning Programmes Author | Project |

The assessment criteria adopted at the Workshop was to review each system and structure type within the system against four decommissioning options:

- Structures being re-used for Quad 204 duty;
- Structures being Suspended Long Term & preserved on the seabed until Quad 204 EoFL;
- Structures being decommissioned insitu as part of Phase 1 Decommissioning;
- Structures being recovered & recycled as part of Phase 1 Decommissioning;

Each option and structure was subsequently assessed against the following criteria:

- Technical Risk;
- Safety Risk;
- Environmental Impact;
- Societal Impact;
- Economic Risk;

3.1 Assessment Criteria

The assessment criteria and aspects selected for the CA(Table 3.2) were adapted from the suggested matrix in the DECC guidance notes.

Table 3.2 Assessment criteria and aspects for options assessment

| Assessment criteria | Aspect |
|---------------------|---|
| Technical | Risk of major project failure |
| | Technical complexity and challenges |
| Safety | Risk to personnel undertaking the decommissioning |
| | Risk to other users of the sea (e.g. fishing vessels) |
| | Risk to those on land undertaking the decommissioning |
| | High consequence events |
| Environmental | Atmospheric emissions |
| | Discharges to sea |
| | Waste management |
| | Resource consumption/ Recycle Value |
| | Disturbance to seabed / land |
| | Accidental spills |
| | Noise underwater and onshore |
| Societal | Fisheries impact (long term) |
| | Community disturbance |
| | Local employment |
| | Stakeholder Reaction |
| Economic | Cost |
| | Uncertainties |

3.2 Comparative Impact

Each of the options was assessed against the assessment criteria/ aspects, with the comparative magnitude for each obtained using the screening criteria shown in Table 3.3

Table 3.3 Comparative impact

| Performance | Comparative impact |
|--------------|--------------------|
| Best Option | Lowest impact |
| | Moderate impact |
| Worst Option | Highest impact |

It is important to highlight that the assessment is comparative and that options assessed as “high” does not denote high risk or high impact. It merely identified the options being the highest from those available for assessment.

Some infrastructure could not be comparatively assessed across all decommissioning options due to

- There being only one technically feasible option, or;
- Specific options not being applicable

Summary tables in Section 4.0 identify where options could not be assessed.

4.0 COMPARATIVE ASSESSMENT CONCLUSIONS

The following is a summary of the CA conclusions by system and by structure type

4.1 Oil Production System

An overview is provided in sections 4.1.1 to 4.1.4 below. However the summary Table 4-1 in section 4.1.5 provides more information.

Appendix A also provides tabulated outcome from the CA Workshop by criteria.

A list of all existing structures associated with the Oil Production System in the field is included in **Appendix B**

4.1.1 Oil Production Flowlines & FTAs

The flowlines & FTAs cannot be re-used for Quad 204 duty due to long term integrity concerns the re-use option was deemed not applicable to the CA, the options that were assessed were; suspend long term; decommission insitu or recover for recycle.

The conclusion of the CA was that to suspend long term for decommissioning at end of Quad 204 EoFL was the best option for all criteria.

4.1.2 Oil Production Manifold M1D

Re-use is identified as the best option for the manifolds across all assessment criteria. Ten (10) out of the eleven (11) manifolds in the field are to be re-used for Quad 204 duty, only one manifold, M1D near to the Central Drill centre, is currently not identified for re-use.

The size of MID manifold means that it cannot be decommissioned insitu, so this option was deemed not applicable during the CA Workshop.

The options that were assessed were; re-use for Quad 204; suspend long term; recover and re-cycle.

Due to the size, weight and location of the manifold, adjacent to live systems, recovery and recycle was identified as the worst case option for all criteria.

Both re-use and long term suspension options were identified as of equally low risk options, across all criteria.

4.1.3 Oil Production Risers & RETs

Since the risers have already been identified as having current integrity problems and the project decision has been made to replace the re-use option was deemed not applicable. The location of the existing risers and RETs will clash with and impede the installation of the new risers, therefore the options associated with long term suspension and decommission in situ were deemed as not applicable for these structures.

Recovery and recycle is identified as the only technically feasible option for decommissioning of these structures and therefore other options were not comparatively assessed. Observations were made and recorded on the risks involved, with recovery and recycle, for the other criteria and are recorded in the summary Table 4-1 for information.

4.1.4 Production Jumpers

Re-use is identified as the best option for the production jumpers across all assessment criteria. Fifty-eight (58) out of the seventy-six (76) production jumpers in the field are to be re-used for Quad 204 duty, leaving only eighteen (18) jumpers that cannot be re-used as they are not the correct length for the revised field configuration. Where jumpers cannot be re-used, they will be replaced by new longer jumpers

The location of the existing redundant jumpers will clash with and impede the installation of the new jumpers, therefore the options associated with long term suspension and decommission in situ were deemed as not applicable for these structures.

Recovery & recycle is identified as the only technically feasible option for decommissioning of these structures that must be replaced and they were not comparatively assessed. Observations were made and recorded on the risks involved for the other criteria and are recorded in the summary Table 4-1 for information.

4.1.5 Summary Table of Comparative Assessment Workshop Outputs – Oil Production System

Key to colours used:

| | | | | |
|----------------------------------|--|--------------------------|---------------|--------------------------|
| Only technically feasible option | Option NOT APPLICABLE - Cannot be included in Comparative Assessment | Low risk - Better Option | Moderate Risk | High Risk - Worst Option |
|----------------------------------|--|--------------------------|---------------|--------------------------|

Table 4-1 Summary of Oil Production System Comparative Assessment

| STRUCTURE | CRITERIA | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
|---|---------------|--|---|---|---|
| Flowlines and Flowline Termination Assemblies | TECHNICAL | Not applicable - Predicted life of existing flowlines is less than Quad204 requirement (long term integrity). Replace now rather than in future. | Ongoing monitoring only, routine operations. | Would require removal of FTAs and Trenching Flowlines. High - Technical Risk in deep water | High risk - would involve cutting flowlines using heavy shears in deep water |
| | SAFETY | Not applicable due to technical constraints - option not comparatively assessed | No intervention required, nothing returned to shore. Ongoing monitoring only, routine operations. | More work involved if intervention required (ploughing, trenching, disconnections). Moderate if trenched Low if not. (FTAs would be recovered if flowlines trenched). | High risk due to short term project intervention, though no long term monitoring/intervention required. |
| | ENVIRONMENTAL | Not applicable due to technical constraints - option not comparatively assessed | Small incremental increase in emissions associated with a monitoring vessel. No incremental increase of discharges to sea, Not losing resources and no additional resources being consumed. No significant seabed disturbance. No activity likely to lead to spills. No activity leading to noise above existing baseline | Depending on type of interventions required, potentially multiple vessels used with associated emissions. Contents of lines are released to sea over time. FTAs would be recovered recycled. Materials left offshore would be lost resource. Increased corridor of seabed disturbance if trenching required. Some noise associated with the cutting of the FTAs | Anticipate more than a season to carry out recovery operations. Contents of lines may be released to sea during recovery. Potential for film of oily waste inside lines being recovered to shore. Increased corridor of seabed disturbance anticipated during recovery. Large number of structures to be recovered. Increased risk of loss of well containment from dropped objects during recovery operations. Risk will reduce at Quad204 EoFL due to wells being abandoned |
| | SOCIETAL | Not applicable due to technical constraints - option not comparatively assessed | Increase infrastructure on seabed, but in existing corridors. No incremental increase in waste coming onshore. Minimal reaction from stakeholders anticipated. | Potentially trench and bury however would not change from current operations and surrounding infrastructure. FTAs would be removed. Potential for negative stakeholder reaction. | No impacts as lines occur in existing corridors. Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. Minimal reaction from stakeholders anticipated. Possibility of some additional work created offshore and onshore. |
| | ECONOMIC | Not applicable due to technical constraints - option not comparatively assessed | Low relative cost | Moderate relative cost | High relative cost |

| STRUCTURE | CRITERIA | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
|--------------|---------------|---|---|--|---|
| Manifold M1D | TECHNICAL | Assuming compatibility for new Quad 204 duty, ROV intervention would be required to replumb the manifold. | No intervention Ongoing monitoring required but routine operations. | Not Applicable - Manifold structure not permitted to be left insitu | Removes opportunity for future use Access difficulty to lift due to proximity of Quad204 infrastructure |
| | SAFETY | ROV intervention would be required to replumb manifold, no material handling on deck. No heavy lifts required, nothing returned to shore. No change to current operations. Within 500 m safety zone | ROV intervention would be required to replumb manifold, no material handling on deck. No heavy lifts required, nothing returned to shore. No change to current operations. Within 500 m safety zone | Not applicable due to technical constraints - option not comparatively assessed | Heavy lift- 70 Te manifold potential dropped object/ risk to wells. Risk will reduce at Quad204 EoFL due to adjacent wells being abandoned. |
| | ENVIRONMENTAL | No significant additional emissions or discharges to sea. No additional resource being used as items will be reused No significant seabed disturbance. No activity likely to lead to spills. No activity leading to noise above existing baseline | Small incremental increase in emissions associated with a monitoring vessel. No incremental increase of discharges to sea, Not losing resources and no additional being consumed. No significant seabed disturbance. No activity likely to lead to spills. No activity leading to noise above existing baseline | Not Applicable - due to technical constraints - option not comparatively assessed | Contents of manifold may be released to sea during recovery. Potential for film of oily waste inside being recovered to shore. Increased corridor of seabed disturbance anticipated during recovery. Increased risk of loss of well containment from dropped objects during recovery. |
| | SOCIETAL | No change to current operations | Increase infrastructure on seabed, but in existing corridors. No incremental increase in waste coming onshore. Potential for some negative stakeholder reaction to long term in field suspension | Not Applicable - due to technical constraints - option not comparatively assessed | Potential for chemicals waste inside pipework being recovered to shore. Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. |
| | ECONOMIC | Low relative cost | Moderate relative cost | Not applicable due to technical constraints - option not comparatively assessed | High relative cost |

Table 4-2 Summary of Oil Production System Comparative Assessment (continued)

| STRUCTURE | CRITERIA | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
|-----------------------------------|---------------|--|--|--|--|
| Risers and Riser End Terminations | TECHNICAL | Not applicable - Current Integrity issues means replacement will be required | Not applicable - location will clash and impede installation of new risers/RET's | Not applicable - location will clash and impede installation of new risers/RET's | Only technically feasible option. |
| | SAFETY | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | High risk to personnel due long risers and attachments to be handles on deck Moderate risk on land in relative low numbers of risers to be recovered. |
| | ENVIRONMENTAL | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Some vessel activity involved in their removal and shipping to shore. Contents of risers may be released to sea during recovery operation, will have been flushed and pigged, but likely to be some oily residue back loaded to shore. Increased noise level if piling is used when decommissioning tether anchors. |
| | SOCIETAL | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | No impacts on fishermen as lines occur in existing corridors / safety zone. Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. Possibility of some additional work created offshore and onshore. Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. |
| | ECONOMIC | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | High relative cost |

| STRUCTURE | CRITERIA | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
|--------------------|---------------|---|--|--|--|
| Production Jumpers | TECHNICAL | Some can be reused as are of sufficient length for new infrastructure. Others not fully compatible with new duty due to length. | Not applicable - Where replacements are necessary, location will clash and impede replacement jumpers installation | Not applicable - Where replacements are necessary, location will clash and impede replacement jumpers installation | Optimal technical option for those that cannot be reused. |
| | SAFETY | Multiple ROV interventions given that some system sections will be suspended. No change to current operations. | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | High risk to deck crew due to High number of jumpers to be recovered. However low consequence of dropped objects damage due to size and weight of jumpers |
| | ENVIRONMENTAL | No significant additional emissions or discharges to sea. No additional resource being used as items will be reused. No significant seabed disturbance. No activity likely to lead to spills. No activity leading to noise above existing baseline. | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Contents of jumpers may be released to sea during recovery. Potential for film of oily waste inside being recovered to shore. Increased corridor of seabed disturbance anticipated during recovery. |
| | SOCIETAL | No change to current operations. | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | No impacts on fishermen as lines occur in existing corridors / safety zone. Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. Possibility of some additional work created offshore and onshore. Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. |
| | ECONOMIC | Low relative cost | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | High relative cost |

4.2 Controls System

An overview is provided in sections 4.2.1 to 4.2.4 below. However summary Table 4-2 in section 4.2.5 provides more information.

Appendix A also provides tabulated outcome from the CA Workshop by criteria.

A list of all existing structures associated with the Control System in the field is included in **Appendix B**

4.2.1 Control Distribution Assemblies (CDAs)

Re-use is identified as the best option for the CDAs across all assessment criteria. Four (4) out of the eight (8) CDAs in the field are to be re-used for Quad 204 duty; the four (4) that cannot be re-used are not compatible with the new Quad 204 duty and must be replaced.

The location of the existing redundant CDAs will clash with and impede the installation of the new CDAs, therefore the options associated with long term suspension and decommission insitu were deemed as not applicable for these redundant structures.

Recovery & recycle is identified as the only technically feasible option for decommissioning of the CDAs that cannot be re-used and other options were not comparatively assessed. Observations were made on the risks involved for the other criteria on the recovery and recycle option, these are recorded and in summary Table 4-2 below for information.

4.2.2 Fly to Place Connecters (FTP)s

Re-use is identified as the best option for the FTPs across all assessment criteria where they are compatible with the new duty. However only forty-four (44) out of the ninety-four (94) FTPs in the field are to be re-used for Quad 204 duty, leaving fifty (50) FTPs that cannot be re-used as they are either not the correct length for the revised field configuration or do not have the required functionality for the Quad 204 duty. Where FTPs cannot be re-used, they will be replaced by new FTPs

Some redundant FTPs are known to be entangled with other FTPs or jumpers that are to be re-used for Quad 204 duty, in such instances the CA has identified that long term suspension is the best option for the redundant FTPs.

Overall the CA concluded that leaving redundant FTPs in long term suspension was the best option but recognises that the location of some existing redundant FTPs will clash with and impedes the installation of the new FTPs and in these instances recovery and recycle is identified as the best option.

4.2.3 Static Umbilicals & UETs

All Ten (10) static umbilicals and twenty (20) UETs are not compatible to perform the functions required for Quad 204 duty and a project decision has already been made to replace them. The option to re-use these structures has been deemed not applicable for the CA; the options that were assessed were; suspend long term; decommission insitu or recover for recycle.

The conclusion of the CA was that to suspend long term for decommissioning at Quad 204 EoFL was the best option for all criteria.

4.2.4 Dynamic Umbilicals & DUTAs

Since two out of the three existing dynamic umbilicals have existing functioning faults and the 3rd umbilical cannot be stored (wet or dry) without risking damage, the Quad 204 project have decided to replace all 3 dynamic umbilicals, the re-use option is deemed not applicable for these structures.

The location of the existing redundant dynamic umbilicals and DUTA will clash with and impede the installation of the new umbilicals, therefore the options associated with long term

suspension and decommission in situ were also deemed as not applicable for these structures.

Recovery & recycle is identified as the only technically feasible option for decommissioning of these structures, CA was therefore not carried out.

4.2.5 Summary Table of Comparative Assessment Workshop Outputs – Control System

Table 4-3 Summary of Control System Comparative Assessment

| STRUCTURES | CRITERIA | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
|---------------------------------|---------------|---|---|---|---|
| Control Distribution Assemblies | TECHNICAL | 4 CDAs are compatible and are being re-used for Quad 204. Remaining 4 CDAs are not compatible with new duty and must be replaced | Location will clash and impede installation of new CDA | Location will clash and impede installation of new CDA, Structures not permitted be left insitu | Inherent dropped object risk to adjacent Quad204 retained infrastructure during recovery |
| | SAFETY | No change to safety risk | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Significant material handling on deck and potential for methanol in the pipework, |
| | ENVIRONMENTAL | No additional emissions, discharges, spills, seabed disturbance or increased noise levels anticipated. | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Potential discharge to sea, chemicals in pipework to be dealt with onshore, increased seabed disturbance |
| | SOCIETAL | No change to current operations | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Potential for chemicals waste inside pipework being recovered to shore. Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. |
| | ECONOMIC | Low relative cost | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Low - due small number and relatively small size of items to be recovered |
| Fly to Place Connectors | TECHNICAL | Some can be reused as are of sufficient length for new infrastructure. Others not fully compatible with new duty due to length and will be replaced | Small amount of FTPs not easily recovered due to entanglement with other equipment (jumpers) will be left long term suspended. Cannot be lifted up as recovery will damage adjacent infrastructure to be reused for Quad 204. | Location will clash and impede installation of new FTP | No technical difficulties anticipated for majority of FTPs |
| | SAFETY | No change to safety risk | No change to safety risk | Not Applicable - due to technical constraints - option not comparatively assessed | Cores may contain methanol and other chemicals. Increase handling risk on deck and onshore. Increased potential for dropped object in vicinity of drill centres |
| | ENVIRONMENTAL | No additional emissions, discharges, spills, seabed disturbance or increased noise levels anticipated. | No additional emissions, discharges, spills, seabed disturbance or increased noise levels anticipated. | Not Applicable - due to technical constraints - option not comparatively assessed | Potential discharge to sea, chemicals in cores to be dealt with onshore |
| | SOCIETAL | No change to current operations | Increase infrastructure on seabed, but in existing corridors. No incremental increase in waste coming onshore. Potential for some negative stakeholder reaction to long term in field suspension | Not Applicable - due to technical constraints - option not comparatively assessed | Large volume of FTPs to be recovered. Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. |
| | ECONOMIC | Low relative cost | Moderate relative cost | Not Applicable - due to technical constraints - option not comparatively assessed | High relative cost |

| STRUCTURES | CRITERIA | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
|---|---------------|--|--|--|---|
| Static Umbilicals & Umbilical End Terminations | TECHNICAL | Option for reuse is limited. Existing umbilicals don't provide full functionality required for Quad204 duty. | Retaining existing umbilicals available on location provides contingency in case of long term failure of new Quad204 umbilicals. | Would require removal of UETs and Trenching umbilicals. Early decommissioning removes contingency for re-use, if failure of Quad204 umbilicals | Technical risks include those associated managing methanol and chemicals trapped cores How could this contained when umbilical is cut Early recovery also removes contingency for re-use, if failure of Quad204 umbilicals |
| | SAFETY | Not Applicable - due to technical constraints - option not comparatively assessed | No change to safety risk | Moderate - handling UETs on deck and onshore and Trenching umbilicals. | Cores may contain methanol and other chemicals. Increase handling risk on deck and onshore. Increased potential for dropped object in vicinity of drill centres |
| | ENVIRONMENTAL | Not Applicable - due to technical constraints - option not comparatively assessed | No additional emissions, discharges, spills, seabed disturbance or increased noise levels anticipated. | Significant disturbance to seabed in trenching and burying, UETs would be recovered. | Potential discharge to sea, chemicals in umbilical cores and Duta pipework to be dealt with onshore. Potential dropped object risk could cause loss of containment at adjacent wellheads |
| | SOCIETAL | Not Applicable - due to technical constraints - option not comparatively assessed | Increase infrastructure on seabed, but in existing corridors. No incremental increase in waste coming onshore. Potential for some negative stakeholder reaction to long term in field suspension | UETs would be recovered. | Potential for chemicals waste inside lines being recovered to shore Large number of structures to be recovered. Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. |
| | ECONOMIC | Not Applicable - due to technical constraints - option not comparatively assessed | Moderate relative cost | High relative cost | Limited vessel availability and weather window extensive items to be recovered |
| Dynamic Umbilicals and Dynamic Umbilical Termination Assemblies | TECHNICAL | Not fully compatible with new duty. Also question w.r.t. performance problems already evident in of 2 of the 3 existing umbilicals. Also uncertainty w.r.t maintaining integrity of 3rd umbilical if wet stored or after reeling if recovered for dry storage. | Location will clash and impede installation of new dynamic umbilicals /DUTAs | Location will clash and impede installation of new dynamic umbilicals /DUTAs | Only technically feasible option. (existing 3rd umbilical may be retained as a spare onshore) |
| | SAFETY | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed |
| | ENVIRONMENTAL | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed |
| | SOCIETAL | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed |
| | ECONOMIC | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed |

4.3 Gas Systems

A list of existing structures associated with the Gas systems in the field is included in **Appendix B**

This list identifies that the vast majority of existing structures are to be re-used for Quad 204 duty. The structures associated with the gas disposal route, whilst not planned to be re-used at Quad 204 start up are to be retained suspended in place as contingency use for future Quad 204 duty.

There are only two structures in the existing gas system that are not to be reused.

- The 8" dia. Gas Lift Riser from the FPSO to FTAF11 – 749 m long
- The 8" dia. Gas Import/ Export Riser from FPSO to manifold M31 – 721 m long

Similar to the production risers, these gas risers have already been identified as having current integrity problems and the project decision has been made to replace. The location of the existing risers will clash with and impede the installation of the new risers, therefore the options associated with long term suspension and decommission in situ were deemed as not applicable for these structures.

Recovery & recycle is identified as the only technically feasible option for decommissioning of these structures and therefore other options were not comparatively assessed. The observed risks for other criteria recorded in Table 4-1 for the recovery of the production risers will be similar for the gas risers.

4.4 Water Injection System

A list of existing structures associated with the WI system in the field is included in **Appendix B**

This list identifies that the vast majority of existing structures are to be re-used for Quad 204 duty. The only structures in the existing WI system that are not to be reused are;

- 3 water injection risers
- 1 water injection RET
- 3 water Injection Jumpers

An overview of the conclusions from the CA is provided in sections 4.4.1 to 4.4.2 below. However see summary Table 4-4 in section 4.4.3 provides more information.

Appendix A also provides tabulated outcome from the comparative assessment workshop by criteria.

4.4.1 WI Risers & RET

Since the risers have already been identified as having current integrity problems and the project decision has been made to replace, the re-use option was not assessed. The location of the existing risers and RET will clash with and impede the installation of the new risers, therefore the options associated with long term suspension and decommission in situ were deemed as not applicable for these structures.

Recovery & recycle is identified as the only technically feasible option for decommissioning of these structures and therefore other options were not comparatively assessed. The observed risks for other criteria recorded in Table 4-1 for the recovery of the production risers will be similar for the WI risers except for the environmental risks associated with the production risers. Since no hydrocarbons are anticipated in the WI risers the risk of discharges to sea is low.

4.4.2 WI Jumpers

Re-use is identified as the best option for the WI jumpers across all assessment criteria. Thirty-six (36) out of the thirty-nine (39) WI jumpers in the field are to be re-used for Quad 204 duty, leaving only three (3) jumpers that cannot be re-used as they are not the correct length for the revised field configuration. Where jumpers cannot be re-used, they will be replaced by new longer jumpers.

The location of the existing redundant jumpers will clash with and impede the installation of the new jumpers, therefore the options associated with long term suspension and decommission in situ were deemed as not applicable for these structures.

Recovery & recycle is identified as the only technically feasible option for decommissioning these structures and they were therefore not comparatively assessed. Observations were made and recorded on the risks involved for the other criteria and are detailed in Table 4.4 in section 4.4.3.

4.4.3 Summary Table of Comparative Assessment Workshop Outputs – Water Injection System

Key to colours used:

| | | | | |
|---|--|--------------------------|---------------|--------------------------|
| <u>Only technically feasible option</u> | Option NOT APPLICABLE - Cannot be included in Comparative Assessment | Low risk - Better Option | Moderate Risk | High Risk - Worst Option |
|---|--|--------------------------|---------------|--------------------------|

Table 4-4 Summary of Water Injection System Comparative Assessment

| CONTROL SYSTEMS | CRITERIA | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
|-------------------------|---------------|--|---|---|---|
| WI RISERS and RET | TECHNICAL | Not applicable - Current Integrity issues with the risers means replacement will be required | Not applicable - location will clash and impede installation of new risers | Not applicable - location will clash and impede installation of new risers | <u>Only technically feasible option.</u> |
| | SAFETY | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> |
| | ENVIRONMENTAL | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> |
| | SOCIETAL | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> |
| | ECONOMIC | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> |
| WATER INJECTION JUMPERS | TECHNICAL | 36 existing WI jumpers are being re-used for Quad204 duty. However 3 jumpers not re-useable as do not have sufficient length for new configuration | Where replacement jumpers are necessary, location of existing jumpers will clash and impede replacement jumpers installation. Therefore cannot be suspended long term | Where replacement jumpers are necessary, location of existing jumpers will clash and impede replacement jumpers installation. Therefore cannot be decommissioned insitu | Recovery of the jumpers is optimal technical option for those that cannot be reused. |
| | SAFETY | No intervention anticipated for re-used jumpers. Therefore no increased risk levels. | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Only 3 jumpers to be recovered therefore moderate deck handling risk and risk when returned to shore. No risk reduction to other sea users as recovered jumpers occur in existing corridors and are to be replaced and potential to cause a major event is low. |
| | ENVIRONMENTAL | No increased emissions, discharges, seabed/land disturbance or increased noise for re-used jumpers. | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Contents of WI Jumpers are benign. Only 3 jumpers (340m total length) recovered for re-use (spares) or recycle. Some seabed disturbance anticipated during recovery operations, small number of worksites. Localised disturbance and noise from cutting and lifting activity. |
| | SOCIETAL | No change to current operations. | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Recovered materials will go to licensed sites. Low key stakeholder reaction anticipated, general acceptance of decomm programme at stakeholder engagement. |
| | ECONOMIC | Low relative cost | Not Applicable - due to technical constraints - option not comparatively assessed | Not Applicable - due to technical constraints - option not comparatively assessed | Relatively Low cost as only 3 jumpers recovered. Minor scope with no uncertainties |

4.5 Other Structures

There are a number of other structures and associated apparatus that have not been considered as part of Quad 204 Project:

- Grout Bags
- Mattresses
- Redundant PWRI pump skids (2 off) located in the vicinity of the Central Drill centre, but never commissioned
- Redundant Anode Skids (2 off) installed to provide protection to Risers in the vicinity of the FPSO,

These structures were assessed as part of the CA Workshop considering the same options as for other structures. An overview is provided in sections 4.5.1 to 4.5.4 below. However summary Table 4-5 in section 4.5.5 provides more information.

Appendix A also provides tabulated outcome from the comparative assessment workshop by criteria.

4.5.1 Grout Bags

These were installed when the original infrastructure was installed to stabilise and secure FTPs and flexible jumpers.

Re-use is identified as the best option for the Grout bags across all assessment criteria where they do not need to be relocated. However there are technical difficulties in re-use of grout bags in different locations. Grout bags mould and set in location after installed and as such are not appropriate for re-use in other configurations. Where grout bags are installed on equipment to be reused for Quad 204 without modification or relocation then they will be left as is.

If the grout bags are located on structures that are to be removed or relocated it is unlikely they can be re-used. The CA concluded that where grout bags cannot remain in use in existing locations, long term suspension or decommissioning insitu are equally good options for redundant grout bags.

The project intends to recover grout bags associated with other structures being recovered, but will utilise baskets to minimise deterioration and break-up of the bags during recovery.

4.5.2 Mattresses

These were installed when the original infrastructure was installed to stabilise and protect flowlines and other fixed structures and also for support at pipe crossings. It is understood there is approximately 144 mattresses in the field.

Many of the mattresses are supporting or protecting infrastructure that is to be re-used for Quad 204 duty and as such will be re-used.

Others are beneath and supporting structures that are to be left in long term suspension and therefore will be retained in this duty.

The CA concluded that re-use for Quad 204 duty, suspend in place and decommission insitu are all equally good options. Although societal impact in decommissioning insitu is not as good due to no creation in new jobs in recycling mattresses and potentially adverse stakeholder reaction to leaving mattresses on the seabed.

The CA concluded that recovery of mattresses during Phase 1 decommissioning is the worst option, due to potential break up of the mattresses during recovery and the potential for dropped objects resulting in damage to adjacent infrastructure that is planned to be re-used for Quad 204 duty. If mattresses are to be recovered it is better to wait until Quad 204 EoFL, when damage to adjacent infrastructure would not be an issue.

4.5.3 Produced Water Re-injection (PWRI) pump skids

There are two large structural frames (70te each approx) located on the seabed within the existing flowlines corridors at the central drill centre. These structures were installed as part of a PWRI Project that never progressed to the commissioning stage. There are no pumps on the skids and there are no interconnecting facilities to the Schiehallion infrastructure. No hydrocarbons or other chemicals have ever been introduced to these skids. They have been on the seabed in a suspended state for a number of years and it is recorded that the skids were also damaged during installation.

The skids have no functionality and have no potential reuse. The size and location of the skids means that they could not be decommissioned insitu. Therefore re-use and decommissioning insitu were not assessed as options.

The CA has concluded that attempting recovery of these skids with live wellheads in the vicinity and adjacent pipelines planned for re-use by Quad 204 is high risk and that long term and continued suspension of these structures to Quad 204 EoFL is the best option from a technical, safety and environmental point of view.

4.5.4 Anode Skids

There are two large and redundant anode skids (Structural frames) on the seabed near to the existing FPSO location. These structures are of no value to Quad 204 project as they can no longer fulfil their original function. These structures will not be replaced. However their location could impede the installation of the new risers, the only technically feasible option will be to recover and recycle these skids. As a result of this conclusion no CA was therefore carried out.

Although large and heavy structures, once the existing risers have been removed there is no adjacent infrastructure at risk from dropped objects and it is therefore the Quad 204 project plan to recover these skids when the risers are being recovered.

4.5.5 Summary Table of Comparative Assessment Workshop Outputs – Other Structures

Key to colours used:

| | | | | |
|----------------------------------|--|--------------------------|---------------|--------------------------|
| Only technically feasible option | Option NOT APPLICABLE - Cannot be included in Comparative Assessment | Low risk - Better Option | Moderate Risk | High Risk - Worst Option |
|----------------------------------|--|--------------------------|---------------|--------------------------|

Table 4-5 Summary of Other Structures Comparative Assessment

| STRUCTURES | CRITERIA | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
|------------|---------------|---|--|--|--|
| Grout bags | TECHNICAL | Where grout bags are installed on equipment to be reused for Quad 204 without modification or relocation then they will be left as is. If associated with structures to be removed or relocated it is unlikely they can be reused. Existing Grout bags will not meet required functionality in new locations or on new equipment and therefore new grout bags will be deployed. | Grout Bags potentially deteriorate as can ropes. | Grout Bags potentially deteriorate as can ropes. | Where recovery of FTP/ jumpers is planned, then associated grout bags will be recovered. However Grout bags not designed for recovery (Deterioration over time). Recovery using baskets will be required. Technically difficult to recover grout bags before Quad 204 EoFL. |
| | SAFETY | No intervention required. No change to Quad 204 operational envelope. Nothing returned onshore. | No safety risk to personnel as nothing recovered. No change to Quad 204 operational envelope. Nothing returned onshore. | No safety risk to personnel as nothing recovered. No change to Quad 204 operational envelope. Nothing returned onshore. | Some lifting operations (baskets), No real reduction in risk for other sea users as within Quad 204 operational envelope.. Handling, recycling onshore will be difficult. Low risk of major incident |
| | ENVIRONMENTAL | No significant additional emissions. Benign materials. No increase of discharges to sea. Nothing returned onshore. For re-use read recycle. No seabed or land disturbance. No noise increase anticipated | No significant additional emissions. Benign materials. No increase of discharges to sea. nothing returned onshore. No recycle. No seabed or land disturbance. No noise increase anticipated | No significant additional emissions. Benign materials. No increase of discharges to sea. nothing returned onshore. No recycle. No seabed or land disturbance. No noise increase anticipated | Additional vessel emissions. No increase of discharges to sea, benign materials. Grout likely to be recycled, no significant increase in noise. |
| | SOCIETAL | No change to current operations. Nothing returned onshore - no community disturbance. No additional employment created. Minimal reaction from stakeholders anticipated. | Increase infrastructure on seabed, but in existing corridors / exclusion zones. Nothing returned onshore - no community disturbance. No additional employment created. Minimal reaction from stakeholders anticipated. | Increase infrastructure on seabed, but in existing corridors / exclusion zones. Nothing returned onshore - no community disturbance. No additional employment created. Potential reaction from stakeholders anticipated. | No impact as grout bags occur in existing corridors / exclusion zones, so no additional fishing area available as a result of their removal. Materials returned to licensed site for disposal. Little additional employment created. Minimal reaction from stakeholders anticipated. |
| | ECONOMIC | Low relative cost | Low relative cost | Low relative cost | Moderate relative cost |
| Mattresses | TECHNICAL | Quad 204 project plan to reuse mattresses where possible e.g. in current location. Mattress relocating for reuse could result in mattresses breaking up. Mattresses at crossings or dropped object protection will be left to perform current function. | No technical risk | No technical risk | Possibility of rope failing when trying to recover e.g. potential that could break up during recovery, dropping on to adjacent structures planned for Quad 204 re-use. Moderate |
| | SAFETY | No intervention required. No change to Quad 204 operational envelope. Nothing returned onshore. | No safety risk to personnel as nothing recovered. No change to Quad 204 operational envelope. Nothing returned onshore. | No safety risk to personnel as nothing recovered. No change to Quad 204 operational envelope. Nothing returned onshore. | Possibility of ropes failing when trying to recover e.g. potential that mattresses could break up during recovery, dropped objects. No real reduction in risk for other sea users as within Quad 204 operational envelope. Handling, recycling onshore will be difficult. Moderate risk of dropping mattress on to adjacent structures planned for Quad 204 re-use |
| | ENVIRONMENTAL | No significant additional emissions. Benign materials. No increase of discharges to sea. nothing returned onshore. For re-use read recycle. No seabed or land disturbance. No noise increase anticipated | No significant additional emissions. Benign materials. No increase of discharges to sea. nothing returned onshore. No seabed disturbance. No noise increase anticipated | No significant additional emissions. Benign materials. No increase of discharges to sea. nothing returned onshore. No recycling as left offshore. No noise increase anticipated | Additional vessel emissions. No increase of discharges to sea, benign materials can be recycled, no significant increase in noise anticipated. |
| | SOCIETAL | No change to current operations. Nothing returned onshore - no community disturbance. No additional employment created. Minimal reaction from stakeholders anticipated. | Increase infrastructure on seabed, but in existing corridors / exclusion zones. Nothing returned onshore - no community disturbance. No additional employment created. Minimal reaction from stakeholders anticipated. | Increase infrastructure on seabed, but in existing corridors / exclusion zones. Nothing returned onshore - no community disturbance. No additional employment created. Potential reaction from stakeholders anticipated. | No impacts as mattresses occur in existing corridors, so no additional fishing area available as a result of their removal. Materials can be recycled. Little additional employment created. Minimal reaction from stakeholders anticipated. |
| | ECONOMIC | Low relative cost | Low relative cost | Low relative cost | Moderate relative cost |

Table 4-6 Summary of Other Structures Comparative Assessment (continued)

| STRUCTURES | CRITERIA | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
|--|---------------|--|--|--|--|
| Frames for 2 pumping skids initially installed for PWRI (never commissioned) | TECHNICAL | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Have been in this state for many years. No technical risk | Not applicable - DECC guidelines require large structures to be recovered | Technically difficult, heavy lift, pump frames are damaged. In close proximity to drill centre. |
| | SAFETY | Not applicable due to technical constraints - option not comparatively assessed | No safety risk to personnel as nothing recovered. Large structures and potential risk to trawlers. Nothing returned onshore, no risk to land users. | Not applicable due to technical constraints - option not comparatively assessed | Heavy lift of damaged structures could result in dropped object In close proximity to drill centre potential major escalation. This risk considered sufficient to keep this red overall. Also risk to personnel from potential dropped objects. Early recovery has no real reduction in risk value to sea users as within Quad 204 operational envelope. Large structures would need to be dismantled at quayside before onward transportation for recycle. |
| | ENVIRONMENTAL | Not applicable due to technical constraints - option not comparatively assessed | Some additional emissions monitoring vessel. No increase of discharges to sea. Nothing returned onshore. No seabed or land disturbance. No noise increase anticipated | Not applicable due to technical constraints - option not comparatively assessed | Increased risk of loss of well containment from dropped object during recovery operations. Incremental additional vessel emissions during recovery. No increase of discharges to sea, materials can be recycled. No significant increase in noise anticipated. |
| | SOCIETAL | Not applicable due to technical constraints - option not comparatively assessed | Leaving redundant large structures on seabed, but in existing corridors / exclusions zones. Nothing returned onshore - no community disturbance. No additional employment created. Potential for some negative stakeholder reaction to long term in field suspension | Not applicable due to technical constraints - option not comparatively assessed | No impacts as structures occur in existing corridors, so no additional fishing area available as a result of their removal. Minimal community disturbance associated with returned materials being recycled. Little additional employment created. Minimal reaction from stakeholders anticipated. |
| | ECONOMIC | Not applicable due to technical constraints - option not comparatively assessed | Low relative cost | Not applicable due to technical constraints - option not comparatively assessed | Moderate relative cost |
| 2 anode skids | TECHNICAL | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | <u>Only technically feasible option.</u> Would expect them to be recovered at same time as risers |
| | SAFETY | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> - option not comparatively assessed |
| | ENVIRONMENTAL | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> - option not comparatively assessed |
| | SOCIETAL | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> - option not comparatively assessed |
| | ECONOMIC | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> - option not comparatively assessed |

5.0 CONCLUSIONS AND RECOMMENDATIONS

The main outcomes of the CA workshop are generally as follows:

- Re-use existing infrastructure for Quad 204 duty where possible and practical;
- Limit disturbance and risk of damage to adjacent retained infrastructure during Phase 1 decommissioning by suspending and preserving redundant equipment until Quad 204 EoFL;
- Suspension must be accompanied with preservation and monitoring to ensure future decommissioning options are not compromised;
- Only recover redundant equipment where it is necessary to do so to create space for new Quad 204 equipment;
- Do not decommission redundant equipment insitu during Phase 1 decommissioning as this could increase risk to damage to adjacent retained equipment and also reduces decommissioning options at Quad 204 EoFL.

6.0 APPENDIX A – OPTIONS ASSESSMENT MATRICES

6.1 OIL PRODUCTION SYSTEMS

The CA workshop completed the assessment by criteria for each system. The overall summary sheet is included in Section 4.1.5, Tables 4-1 and 4-2. The summaries were developed from the individual worksheets in this appendix.

6.1.1 Technical Risk

| Assessment Criteria | Aspects | FLOWLINES, FTA'S, MANIFOLD | | | | |
|---------------------|-----------------------------------|----------------------------|---|---|--|--|
| TECHNICAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE | |
| | Risk of Major Project Failure | Flowlines/FTAs | Not applicable - Predicted life of existing flowlines is less than Quad204 requirement (long term integrity). Replace now rather than in future. | Ongoing monitoring required but routine operations. | Would require removal of FTAs and Trenching Flowlines. High - Technical Risk in deep water | High risk - would involve cutting flowlines using heavy shears in deep water |
| | | Manifold M1D | Assuming compatibility for new Quad 204 duty, ROV intervention would be required to replumb the manifold. | Ongoing monitoring required but routine operations. | Not Applicable - Manifold structure not permitted be left insitu | Removes opportunity for future use Access difficulty to lift due to proximity of Quad204 infrastructure |
| | Technical Complexity & Challenges | Flowlines/FTAs | Not applicable - Predicted life of existing flowlines is less than Quad204 requirement (long term integrity). Replace now rather than in future. | Ongoing monitoring required but routine operations. | Would require removal of FTAs and Trenching Flowlines. High - Technical Risk in deep water | High risk - would involve cutting flowlines using heavy shears in deep water |
| | | Manifold M1D | Assuming compatibility for new Quad 204 duty, ROV intervention would be required to replumb the manifold. | Ongoing monitoring required but routine operations. | Not Applicable - Manifold structure not permitted be left insitu | Removes opportunity for future use Access difficulty to lift due to proximity of Quad204 infrastructure |

| Assessment Criteria | Aspects | RISERS, RETs, PRODUCTION JUMPERS | | | | |
|---------------------|-----------------------------------|----------------------------------|--|---|---|---|
| TECHNICAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE | |
| | Risk of Major Project Failure | Risers/RETs | Not applicable - Current Integrity issues means replacement will be required | Not applicable - location will clash and impede installation of new risers/RET's | Not applicable - location will clash and impede installation of new risers/RET's | Only technically feasible option. |
| | | Production jumpers | Applicable where existing are of sufficient length for new infrastructure. Others not fully compatible with new duty due to length - Low risk of major project failure | Where replacements are necessary, location will clash and impede replacement jumpers installation - Low risk of major project failure | Where replacements are necessary, location will clash and impede replacement jumpers installation - Low risk of major project failure | Optimal technical option for those that cannot be reused. |
| | Technical Complexity & Challenges | Risers/RETs | Not Applicable - Integrity related decision that these structures cannot be reused as cannot fulfil duty. | Not applicable - location will clash and impede installation of new risers/RET's | Not applicable - location will clash and impede installation of new risers/RET's | Only technically feasible option. |
| | | Production jumpers | Some can be reused as are of sufficient length for new infrastructure. Others not fully compatible with new duty due to length. | Not applicable - Where replacements are necessary, location will clash and impede replacement jumpers installation | Not applicable - Where replacements are necessary, location will clash and impede replacement jumpers installation | Optimal technical option for those that cannot be reused. |

6.1.2 Safety

| Assessment Criteria | Aspects | | FLOWLINES, FTA'S, MANIFOLD | | | |
|---------------------|--|------------------------------|---|--|---|---|
| | | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| SAFETY | Risk to Personnel | Options | | | | |
| | | Flowlines/ FTAs (production) | Not Applicable - See Technical Risk | Ongoing monitoring only, routine operations. | More work involved if intervention required (ploughing, trenching, disconnections). Moderate if trenched (FTAs would be removed if trenched). Low if not. | High risk due to short term project intervention, though no long term monitoring/intervention required. |
| | Risk to other Users of the Sea | Manifold M1D | ROV intervention would be required to replumb manifold. No material handling on deck. | Ongoing monitoring only, routine operations. | Not Applicable - See Technical Risk | High risk due to short term project intervention, though no long term monitoring/intervention required. |
| | | Flowlines (production) | Not Applicable - See Technical Risk | Increase infrastructure on seabed but within existing operations corridors | Potentially trench and bury however would not change to current operations as Quad204 equipment would be in vicinity. FTAs would be removed. | No benefit in risk reduction as lines occur in corridors of Quad204 structures |
| | Risk to those on Land | Manifold M1D | No change to current operations. Within 500 m safety zone | No change to current operational envelope but increased infrastructure. Within 500 m safety zone | Not Applicable - See Technical Risk | No change to current operations. Within 500 m safety zone |
| | | Flowlines/ FTAs (production) | Not Applicable - See Technical Risk | Nothing returned to shore | FTAs would have to come back | Everything brought back |
| | Potential for high consequence event, e.g. damage to major oil and gas trunk lines, helicopter accident. | Manifold M1D | Nothing returned to shore | Nothing returned to shore | Not Applicable - See Technical Risk | 70 te manifold |
| | | Flowlines/ FTAs (production) | Not Applicable - See Technical Risk | No intervention | More work involved. Extra heavy lifts, SIMOPS | More chance of dropped objects, due to increase volumes of infrastructure being removed |
| | | Manifold M1D | No heavy lifts required | No heavy lifts required | Not Applicable - See Technical Risk | Heavy lift- potential dropped object/ risk to wells |

| Assessment Criteria | Aspects | | RISERS, RETs, PRODUCTION JUMPERS | | | |
|---------------------|--|--------------------|---|-------------------------------------|-------------------------------------|---|
| | | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| SAFETY | Risk to Personnel | Options | | | | |
| | | Risers and RETs | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | High due to short term project intervention, though no long term monitoring/intervention required. |
| | Risk to other Users of the Sea | Production jumpers | Multiple interventions given that some system sections will be suspended. | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | High due to short term project intervention, though no long term monitoring/intervention required. |
| | | Risers and RETs | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | no risk |
| | Risk to those on Land | Production jumpers | No change to current operations. | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | No difference to current operations (low) |
| | | Risers and RETs | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Moderate (due to limited recovery) |
| | Potential for high consequence event, e.g. damage to major oil and gas trunk lines, helicopter accident. | Production jumpers | No change to current operations. | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Moderate (due to limited recovery) |
| | | Risers and RETs | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Location of risers remote from drill centres Adjacent equipment flushed before recovery commences - Low risk |
| | | Production jumpers | Low (no interactions) | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Low (likelihood of dropping smaller objects is lower and potential damage is less) |

6.1.3 Environmental Impact

| Assessment Criteria | Aspects | FLOWLINES, FTA'S, MANIFOLD, PRODUCTION JUMPERS | | | |
|---------------------|--|---|---|---|---|
| ENVIRONMENTAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| | Atmospheric Emissions | No significant additional emissions | Small incremental increase associated with a monitoring vessel. | Depending on type of interventions required, potentially multiple vessels. | Anticipate more than a season to carry out recovery operations. |
| | Discharges to Sea (oily water and chemicals, sand) | No incremental increase of discharges to sea | No incremental increase of discharges to sea | Contents of lines be released to sea over time | Contents of lines may be released to sea during recovery operation |
| | Waste Management | No incremental increase in waste - only shipboard waste | No incremental increase in waste - only shipboard waste | Recovery of ends (e.g. FTAs Manifold) will need be back loaded for recycle | Potential for film of oily waste inside lines being recovered to shore Large number of structures to be recovered |
| | Resource Consumption/ Recycling Value | No additional resource being used as items will be reused. | Not losing resources and no additional being consumed. | Losing resources | Most redundant structures recovered for re-use (spares) or recycle |
| | Disturbance to Seabed / Land | No significant additional disturbance. | No significant additional disturbance. | Increased corridor of seabed disturbance if trenching required | Increased corridor of seabed disturbance anticipated during recovery operations Localised disturbance from cutting and lifting activity |
| | Accidental Spills | No activity likely to lead to spills. Relatively benign inventories or similar to on-going operations | No activity likely to lead to spills. Relatively benign inventories or similar to on-going operations | Option not applicable for manifold. No activity likely to lead to spills. Relatively benign inventories or similar to on-going operations | Unplanned hydrocarbon discharges during flushing/ pigging activity Increased risk of loss of well containment from dropped objects during recovery operations. Risk will reduce at Quad204 EoFL due to wells being abandoned |
| | Noise Underwater and Onshore | No activity leading to noise above existing baseline | No activity leading to noise above existing baseline | Some noise associated with the cutting of the FTAs. | Cutting activities offshore and onshore. |

| Assessment Criteria | Aspects | RISERS, RETS, | | | |
|---------------------|--|-------------------------------------|-------------------------------------|-------------------------------------|--|
| ENVIRONMENTAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| | Atmospheric Emissions | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Some vessel activity involved in their removal, shipping to shore and movements onshore. |
| | Discharges to Sea (oily water and chemicals, sand) | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Contents of lines may be released to sea during recovery operation, but will have been flushed and pigged. |
| | Waste Management | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Risers flushed, pigged and cleaned before disconnection, but likely to be some oily residue, material to be recycled |
| | Resource Consumption/ Recycling Value | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Risers recovered to shore for recycling |
| | Disturbance to Seabed / Land | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Minor corridor of seabed disturbance resulting from laying down, removal and storing activity |
| | Accidental Spills | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Risers flushed, pigged and cleaned before disconnection. No change to normal operations from vessels used. |
| | Underwater noise associated with removal of UTC and pile | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | If piling is used - High, But if cut away - Moderate. Assuming worst case - High. |

6.1.4 Societal Impact

| Assessment Criteria | Aspects | FLOWLINES, FTA'S, MANIFOLD, PRODUCTION JUMPERS | | | |
|---------------------|--|--|--|---|--|
| SOCIETAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| | Fisheries Impact | No change to current operations | Increase infrastructure on seabed, but in existing corridors. | Potentially trench and bury however would not change from current operations and surrounding infrastructure. FTAs would be removed. | No impact as lines occur in existing corridors |
| | Community Disturbance - impacts onshore. | No incremental increase in waste coming onshore (only shipboard waste) | No incremental increase in waste coming onshore (only shipboard waste) | Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. | Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. |
| | Workforce Welfare & Local Employment | No new jobs will result from this option | No new jobs will result from this option | No new jobs will result from this option | Possibility of some additional work created offshore and onshore |
| | Stakeholder Reaction | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. | Potential for negative stakeholder reaction | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. |

| Assessment Criteria | Aspects | RISERS, RETS | | | |
|---------------------|--|-------------------------------------|-------------------------------------|-------------------------------------|--|
| SOCIETAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| | Fisheries Impact | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | No impact as lines occur in existing corridors / safety zone |
| | Community Disturbance - impacts onshore. | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. |
| | Workforce Welfare & Local Employment | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Possibility of some additional work created offshore and onshore |
| | Stakeholder Reaction | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. |

6.1.5 Economic

| Assessment Criteria | Aspects | ALL STRUCTURES | | | | |
|---------------------|---------------------|----------------------------|-------------------------------------|-------------------------------------|-------------------------------------|---|
| ECONOMIC | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE | |
| | Cost | Flowlines/ FTAs | Not Applicable - See Technical Risk | Moderate relative cost | Moderate relative cost | High relative cost |
| | | Manifold M1D | Low relative cost | Moderate relative cost | Not Applicable - See Technical Risk | High relative cost |
| | | Risers/ RETs | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | High relative cost |
| | | Production Jumpers | Low relative cost | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | High relative cost |
| | Uncertainty | Flowlines/ FTAs | Not Applicable - See Technical Risk | Low | Moderate | High - Limited vessel availability and weather window extensive items to be recovered |
| | | Manifold M1D | Low | Low | Not Applicable - See Technical Risk | Low - due to single item to be recovered only |
| | | Risers/ RETs | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | High - Limited vessel availability and weather window extensive items to be recovered |
| | | Production Jumpers | Low | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Low - due small number and relatively small size of items to be recovered |

6.2 CONTROL SYSTEMS

The CA workshop completed the assessment by criteria for each system. The overall summary sheet is included in Section 4.2.5, Table 4-3. The summary was developed from the individual worksheets in this appendix.

6.2.1 Technical Risk

| Assessment Criteria | Aspects | | CDAs, FTPs | | | |
|---------------------|-----------------------------------|----------------------------|---|--|--|--|
| | | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| TECHNICAL RISK | Risk of Major Project Failure | Outline Description | | | | |
| | | Dynamic umbilicals / DUTAs | Not Applicable - Not fully compatible with new duty. Also question w.r.t. performance problems already evident in 2 of the 3 existing umbilicals. Also uncertainty w.r.t maintaining integrity of 3rd umbilical if wet stored or after reeling if recovered for dry storage. | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | Only technically feasible option. (existing 3rd umbilical may be retained as a spare onshore) |
| | | CDAs | No risk of major project failure | Not applicable - location will clash and impede installation of new CDA | Not applicable - location will clash and impede installation of new CDA | High - due to inherent dropped object risk to adjacent Quad 204 retained infrastructure during recovery |
| | Technical Complexity & Challenges | FTPAs | No risk of major project failure | FTPAs not easily recovered due to entanglement with other equipment (jumpers) will be left long term suspended. Cannot be lifted up as recovery will damage infrastructure to be reused for Quad 204. - Still Low risk | Not Applicable - FTPAs not permitted be left insitu | Low. Optimal option for those that cannot be reused and can be reused. |
| | | CDAs | 4 CDAs are compatible and are being re-used for Quad 204. Remaining 4 CDAs are not compatible with new duty and must be replaced - Low | Not applicable - location will clash and impede installation of new CDA | Not applicable - location will clash and impede installation of new CDA | High Risk - due to inherent dropped object risk to adjacent Quad 204 retained infrastructure during recovery |
| | | FTPAs | Low. Some can be reused as are of sufficient length for new infrastructure. Others not fully compatible with new duty due to length and will be replaced | Small amount of FTPAs not easily recovered due to entanglement with other equipment (jumpers) will be left long term suspended. Cannot be lifted up as recovery will damage infrastructure to be reused for Quad 204. - Still Low risk | Not Applicable - FTPAs not permitted be left insitu | No technical difficulties anticipated for majority of FTPAs |
| 6 | | | | | | |

| Assessment Criteria | Aspects | | STATIC UMBILICALS, UETs | | | |
|---------------------|-------------------------------|-----------------------------------|---|--|---|--|
| | | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| TECHNICAL RISK | Risk of Major Project Failure | Outline Description | | | | |
| | | Risk of Major Project Failure | No risk of major project failure | No risk of major project failure | No risk of major project failure | No risk of major project failure |
| | | Technical Complexity & Challenges | High - Option for reuse is limited. Existing umbilicals don't provide full functionality required for Quad204 duty. | Retaining existing umbilicals available on location provides contingency in case of long term failure of new Quad204 umbilicals. | Would require removal of UETs and Trenching umbilicals. Moderate - Technical Risk <u>Removes contingency for re-use,</u> if failure of Quad204 umbilicals | Moderate technical risks include those associated with methanol and chemicals trapped in chemical cores (How is this contained) Removes contingency for re-use, if failure of Quad204 umbilicals |
| 6 | | | | | | |

6.2.2 Safety

| Assessment Criteria | Aspects | CDAs, FTPs | | | | |
|---------------------|---|----------------------------|--|--|--|--|
| | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE | |
| SAFETY | Options | | | | | |
| | Risk to Personnel | Dynamic umbilicals / DUTAs | Not Applicable - Not fully compatible with new duty. Also question w.r.t. performance problems already evident in of 2 of the 3 existing umbilicals. Also uncertainty w.r.t maintaining integrity of 3rd umbilical if wet stored or after reeling if recovered for dry storage. | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | Only technically feasible option. (existing 3rd umbilical may be retained as a spare onshore) |
| | | FTPAs | No safety risk. | No safety risk. | Not applicable - location will clash and impede installation of new CDA | Chemical cores may contain methanol and other chemicals. Increase handling risk on deck of vessel - High |
| | | CDAs | No safety risk. | Low. ROV operations only - low risk | Not Applicable - FTPs not permitted be left insitu | High Risk - significant material handling on deck and potential for methanol in the pipework |
| | Risk to other Users of the Sea | Dynamic umbilicals / DUTAs | Not Applicable - Not fully compatible with new duty. Also question w.r.t. performance problems already evident in of 2 of the 3 existing umbilicals. Also uncertainty w.r.t maintaining integrity of 3rd umbilical if wet stored or after reeling if recovered for dry storage. | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | Only technically feasible option. (existing 3rd umbilical may be retained as a spare onshore) |
| | | FTPAs | no change to current operations. (Low) | no change to current operations. (Low) | Not applicable - location will clash and impede installation of new CDA | No impact (Low) |
| | | CDAs | No change to current operations. Within 500 m safety zone (Low) | No change to current operational envelope but increased infrastructure. Within 500 m safety zone (Low) | Not Applicable - FTPs not permitted be left insitu | No change to current operations. Within 500 m safety zone (Low) |
| | Risk to those on Land | Dynamic umbilicals / DUTAs | Not Applicable - Not fully compatible with new duty. Also question w.r.t. performance problems already evident in of 2 of the 3 existing umbilicals. Also uncertainty w.r.t maintaining integrity of 3rd umbilical if wet stored or after reeling if recovered for dry storage. | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | Only technically feasible option. (existing 3rd umbilical may be retained as a spare onshore) |
| | | FTPAs | . Low | Low | Not applicable - location will clash and impede installation of new CDA | High potential methanol in the cores |
| | | CDAs | . Low | Low | Not Applicable - FTPs not permitted be left insitu | High (potential methanol) |
| | High consequence event, e.g. damage to major oil and gas trunk lines, helicopter accident | Dynamic umbilicals / DUTAs | Not Applicable - Not fully compatible with new duty. Also question w.r.t. performance problems already evident in of 2 of the 3 existing umbilicals. Also uncertainty w.r.t maintaining integrity of 3rd umbilical if wet stored or after reeling if recovered for dry storage. | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | Only technically feasible option. (existing 3rd umbilical may be retained as a spare onshore) |
| | | FTPAs | Low (no interactions) | Low (no intervention) | Not Applicable - See Technical Risk | Moderate (some lifting operations) |
| | | CDAs | No heavy lifts required. Low | No heavy lifts required. Low | Not Applicable - See Technical Risk | Moderate (some lifting operations, differs to manifolds as further from well heads) |

| Assessment Criteria | Aspects | STATIC UMBILICALS, UETs | | | |
|---------------------|---|--|---|--|--|
| | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| SAFETY | Options | | | | |
| | Risk to Personnel | Option for reuse is limited. Don't have full functionality required. (Low) | Ongoing monitoring but will be of low risk. Routine operations. Low | Would require removal of UETs (handling on deck) and Trenching umbilicals. Moderate | Chemical cores may contain methanol and other chemicals. Increase handling risk on deck of vessel - High |
| | Risk to other Users of the Sea | No change to current operations. (Low) | Increase infrastructure on seabed but within existing corridors (Low) | Potentially trench and bury however not change would risk from current operations (Other adjacent equipment being reused or Quad 204). Low | In general no benefit as lines occur in corridors where Quad204 equipment is being retained For two umbilicals removal may clear existing corridors. Low |
| | Risk to those on Land | Nothing returned | Nothing returned | UETs would have to come back- Moderate | Chemical cores may contain methanol and other chemicals. Increase handling risk onshore. Everything brought back - High |
| | High consequence event, e.g. damage to major oil and gas trunk lines, helicopter accident | Low (no interactions) | Low (no intervention) | More work involved. Extra heavy lifts, SIMOPS (e.g. trenching) Moderate | High - increased potential for dropped object in vicinity of drill centres, due to increase volumes of infrastructure being removed. |

6.2.3 Environmental Impact

| Assessment Criteria | Aspects | CDAs, FTPs, Static Umbilicals and UETs | | | |
|---------------------|--|--|--|-------------------------------------|--|
| ENVIRONMENTAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| | Atmospheric Emissions | No significant additional emissions | Small incremental increase associated with a monitoring vessel. | Not Applicable - See Technical Risk | Relatively easily recovered if not obstructed by other subsea infrastructure. |
| | Discharges to Sea | No incremental increase of discharges to sea | No incremental increase of discharges to sea | Not Applicable - See Technical Risk | Contents of lines may be released to sea during recovery operation |
| | Waste Management | No incremental increase in waste - only shipboard waste | No incremental increase in waste - only shipboard waste | Not Applicable - See Technical Risk | Potential for chemicals waste inside lines being recovered to shore Large number of structures to be recovered |
| | Resource Consumption - focused on loss of resources (material not recovered) | No additional resource being used as items will be reused. | Not losing resources and no additional being consumed. | Not Applicable - See Technical Risk | Most redundant structures recovered for re-use (spares) or recycle |
| | Disturbance to Seabed / Land | No significant additional disturbance. | No significant additional disturbance. | Not Applicable - See Technical Risk | Increased corridor of seabed disturbance anticipated during recovery operations Localised disturbance from cutting and lifting activity |
| | Accidental Spills | No activity likely to lead to spills. Relatively benign inventories or similar to ongoing operations | No activity likely to lead to spills. Relatively benign inventories or similar to ongoing operations | Not Applicable - See Technical Risk | Increased risk of loss of well containment from dropped objects during recovery operations Will reduce at EoFL due to wells being abandoned etc. |
| | Noise Underwater and Onshore | No activity leading to noise above existing baseline | No activity leading to noise above existing baseline | Not Applicable - See Technical Risk | Cutting activities offshore and onshore. |

| Assessment Criteria | Aspects | DYNAMIC UMBILICALS, DUTA | | | |
|---------------------|---------------------|---|---|---|--|
| ENVIRONMENTAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| | All Aspects | Not Applicable - Not compatible with new duty. Also question w.r.t. performance problems already evident in of 2 of the 3 existing umbilicals. Also uncertainty w.r.t maintaining integrity of 3rd umbilical if wet stored or after reeling if recovered for dry storage. | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | Not applicable - location will clash and impede installation of new dynamic umbilicals /DUTAs | <u>Only technically feasible option.</u> (existing 3rd umbilical may be retained as a spare onshore) |

6.2.4 Societal Impact

| Assessment Criteria | Aspects | CDAs, FTPs, STATIC UMBILICALS AND UETs | | | |
|---------------------|--|---|---|-------------------------------------|---|
| SOCIETAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| | Fisheries Impact | No change to current operations | Increase infrastructure on seabed, but in existing corridors. | Not Applicable - See Technical Risk | No impacts as lines occur in corridors, so no additional fishing area available as a result of their removal. |
| | Community Disturbance - impacts onshore. | No incremental increase in waste coming onshore (only shipboard waste) | No incremental increase in waste coming onshore (only shipboard waste) | Not Applicable - See Technical Risk | Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. |
| | Workforce Welfare & Local Employment | Re-use would result in no new jobs | Suspend long term would result in no new jobs | Not Applicable - See Technical Risk | Some work associated with the removal and deconstruction. |
| | Stakeholder Reaction | Minimal reaction from stakeholders anticipated, general acceptance of decomm programme at stakeholder engagement. | Potential for some negative stakeholder reaction to long term in field suspension | Not Applicable - See Technical Risk | Minimal reaction from stakeholders anticipated, general acceptance of decomm programme at stakeholder engagement. |
| | | | | | |

6.2.5 Economic

| Assessment Criteria | Aspects | CDAs, FTPs, Static Umbilicals and UETs | | | | |
|---------------------|---------------------|--|-------------------------------------|-------------------------------------|-------------------------------------|---|
| ECONOMIC | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE | |
| | Cost | CDA's | Low relative cost | Moderate relative cost | Not Applicable - See Technical Risk | High relative cost |
| | | FTP's | Low relative cost | Moderate relative cost | Not Applicable - See Technical Risk | High relative cost |
| | | Static Umbilicals/UET's | Not Applicable - See Technical Risk | Moderate relative cost | Moderate relative cost | High relative cost |
| | Uncertainty | CDA's | Low | Low | Not Applicable - See Technical Risk | Low - due to single item to be recovered only |
| | | FTP's | Low | Not Applicable - See Technical Risk | Not Applicable - See Technical Risk | Low - due small number and relatively small size of items to be recovered |
| | | Static Umbilicals/UET's | Not Applicable - See Technical Risk | Low | Moderate | High - Limited vessel availability and weather window extensive items to be recovered |
| | | | | | | |

6.3 WATER INJECTION SYSTEMS

The CA workshop completed the assessment by criteria for each system. The overall summary sheet is included in Section 4.4.5, Table 4-4. The summary was developed from the individual worksheets in this appendix.

6.3.1 Technical Risk

| Assessment Criteria | Aspects | | ALL STRUCTURES | | | |
|---------------------|-----------------------------------|-----------------------|--|---|---|--|
| | | Structure Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| TECHNICAL RISK | Risk of Major Project Failure | WI Risers and RETs | Not applicable - Current Integrity issues means replacement will be required | Not applicable - location will clash and impede installation of new risers | Not applicable - location will clash and impede installation of new risers | <u>Only technically feasible option.</u> |
| | | WI Jumpers | Low risk of major project failure | Low risk of major project failure | Low risk of major project failure | Low risk of major project failure |
| | Technical Complexity & Challenges | WI Risers and RETs | Not applicable - Current Integrity issues means replacement would be required | Not applicable - location will clash and impede installation of new risers | Not applicable - location will clash and impede installation of new risers | <u>Only technically feasible option.</u> |
| | | WI Jumpers | 36 existing WI jumpers are being re-used for Quad204 duty. However 3 jumpers not re-useable as do not have sufficient length for new configuration | Where replacement jumpers are necessary, location of existing jumpers will clash and impede replacement jumpers installation. Therefore cannot be suspended long term | Where replacement jumpers are necessary, location of existing jumpers will clash and impede replacement jumpers installation. Therefore cannot be decommissioned insitu | Recovery of the jumpers is optimal technical option for those that cannot be reused. |

6.3.2 Safety

| Assessment Criteria | Aspects | | ALL STRUCTURES | | | |
|---------------------|--|---------------------|---|--|--|--|
| | | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| SAFETY | Risk to Personnel | WI Risers and RETs | Not applicable - Current Integrity issues means replacement would be required | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> |
| | | WI Jumpers | 36 existing WI jumpers are being re-used for Quad204 duty. No intervention anticipated. | Where replacement jumpers are necessary, location of existing jumpers will clash and impede replacement jumpers installation. <u>Therefore cannot be suspended long term</u> | Where replacement jumpers are necessary, location of existing jumpers will clash and impede replacement jumpers installation. <u>Therefore cannot be decommissioned insitu</u> | Only 3 jumpers to be recovered therefore moderate deck handling risk |
| | Risk to other Users of the Sea | WI Risers and RETs | Not applicable - Current Integrity issues means replacement would be required | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> |
| | | WI Jumpers | 36 existing WI jumpers are being re-used for Quad204 duty. Re-used jumpers are within existing operational corridors - no change to risk levels | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | No improvement to risk level as recovered jumpers occur in existing corridors and are to be replaced |
| | Risk to those on Land | WI Risers and RETs | Not applicable - Current Integrity issues means replacement would be required | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> |
| | | WI Jumpers | 36 existing WI jumpers are being re-used for Quad204 duty. Re-used jumpers therefore not returned onshore | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Only 3 jumpers (340m total length) to be recovered therefore moderate during onshore disposal |
| | Potential for high consequence event, e.g. damage to major oil and gas trunk lines, helicopter accident. | WI Risers and RETs | Not applicable - Current Integrity issues means replacement would be required | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> |
| | | WI Jumpers | 36 existing WI jumpers are being re-used for Quad204 duty. No intervention anticipated. | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Low risk - Only 3 jumpers to be recovered. |

6.3.3 Environmental Impact

| Assessment Criteria | Aspects | WI JUMPERS | | | |
|---------------------|--|--|--|--|---|
| ENVIRONMENTAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| | Atmospheric Emissions | No significant additional emissions | Where replacement jumpers are necessary, location of existing jumpers will clash and impede replacement jumpers installation. <u>Therefore cannot be suspended long term</u> | Where replacement jumpers are necessary, location of existing jumpers will clash and impede replacement jumpers installation. <u>Therefore cannot be decommissioned insitu</u> | Potentially multiple vessels involved in the removal |
| | Discharges to Sea (oily water and chemicals, sand) | No incremental increase of discharges to sea | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | No incremental increase in releases to sea, contents of WI Jumpers is benign |
| | Waste Management | No incremental increase in waste - only shipboard waste | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Recovered jumpers will be recycled where possible. |
| | Resource Consumption/ Recycling Value | No additional resource being used as items will be reused. | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | 3 jumpers (340m total length) recovered for re-use (spares) or recycle |
| | Disturbance to Seabed / Land | No significant additional disturbance. | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Some seabed disturbance anticipated during recovery operations small number of worksites. Localised disturbance from cutting and lifting activity |
| | Accidental Spills | No activity likely to lead to spills. Benign inventories or similar to on-going operations | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | No activity likely to lead to spills. Relatively benign inventories, vessel activities similar to on-going operations. |
| | Noise Underwater and Onshore | No activity leading to noise above existing baseline | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Cutting activities on and offshore. |

| Assessment Criteria | Aspects | RISERS and RET | | | |
|---------------------|--|---|---|---|--|
| ENVIRONMENTAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| | Atmospheric Emissions | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | <u>Only technically feasible option.</u> |
| | Discharges to Sea (oily water and chemicals, sand) | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Remaining contents of lines (which will have been flushed and pigged) may discharge during recovery operations |
| | Waste Management | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Risers flushed, pigged and cleaned before disconnection, plan for materials to be recycled. |
| | Resource Consumption/ Recycling Value | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Redundant material recovered to be recycled |
| | Disturbance to Seabed / Land | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Minor seabed disturbance resulting from laying down, storing and removal activities |
| | Accidental Spills | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Risers flushed, pigged and cleaned before disconnection. No change to normal operations from vessels used. |
| | Underwater noise associated with removal of UTC and pile | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | If piling is used - High, But if cut away - Moderate. Assuming worst case - High. |

6.3.4 Societal Impact

| Assessment Criteria | Aspects | WATER INJECTION JUMPERS | | | |
|---------------------|--|---|---|---|---|
| SOCIETAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| | Fisheries Impact | No change to current operations | Where replacement jumpers are necessary, location of existing jumpers will clash and impede replacement jumpers installation. Therefore cannot be suspended long term | Where replacement jumpers are necessary, location of existing jumpers will clash and impede replacement jumpers installation. Therefore cannot be decommissioned insitu | No impact as recovered lines occur in existing corridors and are being replaced |
| | Community Disturbance - impacts onshore. | No incremental increase in waste coming onshore (only shipboard waste) | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. |
| | Workforce Welfare & Local Employment | No new jobs will result from this option | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Possibility of some additional work created offshore and onshore |
| | Stakeholder Reaction | Low key reaction anticipated, general acceptance of decomm programme at stakeholder engagement. | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Low key reaction anticipated, general acceptance of decomm programme at stakeholder engagement. |

| Assessment Criteria | Aspects | RISERS and RET | | | |
|---------------------|--|--|--|--|---|
| SOCIETAL | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| | Fisheries Impact | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Only technically feasible option. |
| | Community Disturbance - impacts onshore. | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site. |
| | Workforce Welfare & Local Employment | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Possibility of some additional work created offshore and onshore |
| | Stakeholder Reaction | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Low key reaction anticipated, general acceptance of decomm programme at stakeholder engagement. |

6.3.5 Economic

| Assessment Criteria | Aspects | ALL STRUCTURES | | | | |
|---------------------|---------------------|----------------------------|--|--|--|---|
| ECONOMICS | Outline Description | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE | |
| | Cost | WI Risers and RETs | Not applicable - Current Integrity issues means replacement would be required | Not applicable - location will clash and impede installation of new risers | Not applicable - location will clash and impede installation of new risers | Only technically feasible option. |
| | | WI Jumpers | 36 existing WI jumpers are being re-used for Quad204 duty. However 3 jumpers not re-useable as do not have sufficient length for new configuration | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Relatively Low cost as only 3 jumpers recovered |
| | Uncertainty | WI Risers and RETs | Not applicable - Current Integrity issues means replacement would be required | Not applicable - location will clash and impede installation of new risers | Not applicable - location will clash and impede installation of new risers | Only technically feasible option. |
| | | WI Jumpers | 36 existing WI jumpers are being re-used for Quad204 duty. However 3 jumpers not re-useable as do not have sufficient length for new configuration | Not applicable due to technical constraints - option not comparatively assessed | Not applicable due to technical constraints - option not comparatively assessed | Minor scope with no uncertainties |

6.4 OTHER STRUCTURES

The CA workshop completed the assessment by criteria for each system. The overall summary sheet is included in Section 4.5.5, Table 4-5. The summary was developed from the individual worksheets in this appendix.

6.4.1 Technical Risk

| Assessment Criteria | Aspects | | OTHER STRUCTURES | | | |
|---------------------|-------------------------------------|--|---|--|--|---|
| | | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| TECHNICAL RISK | Risk of Major Project Failure | Outline Description | | | | |
| | | Grout bags | Low risk of causing major project failure | Low risk of causing major project failure | Low risk of causing major project failure | Low risk of causing major project failure |
| | | Mattresses | Low risk of causing major project failure | Low risk of causing major project failure | Low risk of causing major project failure | Possibility of rope failing when trying to recover e.g. potential that could break up during recovery, dropping on to adjacent structures planned for Quad 204 re-use. Resulting damage could delay start up. |
| | | Frames for 2 pumping skids initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Low risk of causing major project failure | Not applicable - DECC guidelines require large structures to be recovered | Technically difficult, heavy lift, pump frames are damaged. In close proximity to drill centre. |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |
| | Technical Complexity and Challenges | Grout bags | Where grout bags are installed on equipment to be reused for Quad 204 without modification or relocation then they will be left as is. If associated with structures to be removed or relocated it is unlikely they can be reused. Existing Grout bags will not meet required functionality in new locations or on new equipment and therefore new grout bags will be deployed. | Grout Bags potentially deteriorate as can ropes. | Grout Bags potentially deteriorate as can ropes. | Where recovery of FTP/ jumpers is planned, then associated grout bags will be recovered. However Grout bags not designed for recovery (Deterioration over time). Recovery using baskets will be required. Technically difficult to recover grout bags before Quad 204 EoFL. |
| | | Mattresses | Quad 204 project plan to reuse mattresses where possible e.g. in current location. Mattress relocating for reuse could result in mattresses breaking up. Mattresses at crossings or dropped object protection will be left to perform current function. | No technical risk | No technical risk | Possibility of rope failing when trying to recover e.g. potential that could break up during recovery, dropping on to adjacent structures planned for Quad 204 re-use. Moderate |
| | | Frames for 2 pumping skids initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Have been in this state for many years. No technical risk | Not applicable - DECC guidelines require large structures to be recovered | Technically difficult, heavy lift, pump frames are damaged. In close proximity to drill centre. |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |
| | | | | | | |

6

6.4.2 Safety

| Assessment Criteria | Aspects | | OTHER STRUCTURES | | | |
|---------------------|--|---|--|--|--|---|
| | Outline Description | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| SAFETY | Risk to Personnel | Grout bags | Where grout bags are installed on equipment to be reused for Quad 204 without modification or relocation then they will be left as is. No intervention required | No safety risk to personnel as nothing recovered. | No safety risk to personnel as nothing recovered. | Some lifting operations (baskets) |
| | | Mattresses | Quad 204 project plan to reuse mattresses where possible e.g. in current location. Mattress relocating for reuse could result in mattresses breaking up. Mattresses at crossings or dropped object protection will be left to perform current function. No intervention required | No safety risk to personnel as nothing recovered. | No safety risk to personnel as nothing recovered. | Possibility of ropes failing when trying to recover e.g. potential that could break up during recovery, dropped objects. |
| | | Frames pump skids, initially installed for PWRI, never commissioned | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | No safety risk to personnel as nothing recovered. | Not applicable - DECC guidelines require large structures to be recovered | Some lifting operations of damaged structures, potential dropped objects on deck |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technical feasible option. Would expect them to be recovered at same time as risers |
| | Risk to other Sea Users | Grout bags | Grout bags are generally located at FTPs and Jumpers and are therefore local to drill centres. No change to Quad 204 operational envelope. | Grout bags are generally located at FTPs and Jumpers and are therefore local to drill centres. No change to Quad 204 operational envelope. | Grout bags are generally located at FTPs and Jumpers and are therefore local to drill centres. No change to Quad 204 operational envelope. | Although recovery reduces total inventory on seabed, No real reduction in risk as within Quad 204 operational envelope. |
| | | Mattresses | Quad 204 project plan to reuse mattresses where possible e.g. in current location. Mattresses at crossings or dropped object protection will be left to perform current function. | Redundant Mattresses will be Quad 204 operational envelope. No additional risk. | Redundant Mattresses will be Quad 204 operational envelope. No additional risk. | Although recovery reduces total inventory on seabed, No real reduction in risk as within Quad 204 operational envelope. |
| | | Frames pump skids, initially installed for PWRI, never commissioned | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Large structures and potential risk to trawlers | Not applicable - DECC guidelines require large structures to be recovered | Recovery reduces risks to trawlers |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |
| | Risk to those on Land | Grout bags | Nothing returned onshore, no risk | Nothing returned onshore, no risk | Nothing returned onshore, no risk | Where recovery of FTP/ jumpers is planned, then associated grout bags will be recovered. However Grout bags are not designed for recovery (Deterioration over time). Handling, recycling onshore will be difficult. |
| | | Mattresses | Nothing returned onshore, no risk | Nothing returned onshore, no risk | Nothing returned onshore, no risk | Possibility of rope failing when transporting e.g. potential that mattresses could break up. Difficult to handle and recycle onshore |
| | | Frames pump skids, initially installed for PWRI, never commissioned | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Nothing returned onshore, no risk | Not applicable - DECC guidelines require large structures to be recovered | Large structures would need to be dismantled at quayside before onward transportation for recycle. |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technical feasible option. Would expect them to be recovered at same time as risers |
| | High consequence event, e.g. damage to major oil and gas trunklines, helicopter accident | Grout bags | Where grout bags are installed on equipment to be reused for Quad 204 without modification or relocation then they will be left as is. No intervention required. | Grout Bags potentially deteriorate as can ropes. | Grout Bags potentially deteriorate as can ropes. | Although Grout bags not designed for recovery, low risk due to size and weight of bags |
| | | Mattresses | Quad 204 project plan to reuse mattresses where possible e.g. in current location. Mattress relocating for reuse could result in mattresses breaking up. Mattresses at crossings or dropped object protection will be left to perform current function. No intervention required | No risk to personnel as nothing disturbed | No risk to personnel as nothing disturbed | Possibility of rope failing when trying to recover e.g. potential that mattresses could break up during recovery, dropping on to adjacent structures planned for Quad 204 re-use. |
| | | Frames pump skids, initially installed for PWRI, never commissioned | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | No risk to personnel as nothing disturbed | Not applicable - DECC guidelines require large structures to be recovered | Heavy lift, large pump frames are damaged. In close proximity to drill centre. Could result in major escalation. |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |

6.4.3 Environmental Impact

| Assessment Criteria | Aspects | OTHER STRUCTURES | | | | |
|---------------------|-----------------------|---|---|--|---|---|
| | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE | |
| ENVIRONMENTAL | Atmospheric Emissions | Outline Description | | | | |
| | | Grout bags | No significant additional emissions | No significant additional emissions, monitoring not required | No significant additional emissions, monitoring not required | Potentially multiple vessels offshore, road transport onshore and machinery used for recycling. |
| | | Mattresses | No significant additional emissions | No significant additional emissions, monitoring not required | Not Applicable - DECC guidance is for removal of mattresses. | Potentially multiple vessels offshore, road transport onshore and machinery used for recycling. |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Additional monitoring vessel emissions | Not Applicable - DECC guidelines require large structures to be recovered | Potentially multiple vessels offshore, road transport onshore and machinery used for recycling. |
| | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered and recycled (where possible) at same time as risers | |
| | Discharges to Sea | Grout bags | No increase of discharges to sea, benign materials | No increase of discharges to sea, benign materials | No increase of discharges to sea, benign materials | No increase of discharges to sea, benign materials |
| | | Mattresses | No increase of discharges to sea, benign materials | No increase of discharges to sea, benign materials | Not Applicable - DECC guidance is for removal of mattresses. | No increase of discharges to sea, benign materials |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | No increase of discharges to sea | Not Applicable - DECC guidelines require large structures to be recovered | Only discharges to sea associated with vessel activities. |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |
| | Waste Management | Grout bags | Nothing returned onshore - no waste | Nothing returned onshore - no waste | Nothing returned onshore - no waste | Benign materials can be recycled |
| | | Mattresses | Nothing returned onshore, no risk | Nothing returned onshore - no waste | Not Applicable - DECC guidance is for removal of mattresses. | Benign materials can be recycled |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Nothing returned onshore - no waste | Not Applicable - DECC guidelines require large structures to be recovered | Benign materials can be recycled |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |

| Assessment Criteria | Aspects | OTHER STRUCTURES | | | | |
|---------------------------|--|--|---|--|--|---|
| | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE | |
| ENVIRONMENTAL (Continued) | Outline Description | | | | | |
| | Resource Consumption/Recycling - focused on loss of resources (material not recovered) | Grout bags | No additional resource being used as items will be reused. | Not losing resource and no additional being used. | Not Applicable - DECC guidance is for removal of mattresses. | Recovered onshore for recycling. |
| | | Mattresses | No additional resource being used as items will be reused. | Not losing resource and no additional being used. | Nothing returned onshore, no recycle | Recovered onshore for recycling. |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Not losing resource and no additional being used. | Not Applicable - DECC guidelines require large structures to be recovered | Recovered onshore for recycling. |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |
| | Disturbance to Seabed / Land | Grout bags | No disturbance | No disturbance | No disturbance | Minimal additional disturbance on seabed as recovery occurs at FTPs and jumpers etc already being removed. Minimal disturbance on land as disposal recycle. |
| | | Mattresses | No disturbance | No disturbance | No disturbance | Minimal additional disturbance on seabed as recovery occurs at FTPs and jumpers etc already being removed. Minimal disturbance on land as disposal recycle. |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | No disturbance | Not Applicable - DECC guidelines require large structures to be recovered | Moderate short term disturbance on seabed anticipated due to size and weight of structures |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |
| | Accidental Spills | Grout bags | Solid Structures / Benign Materials, vessel activity similar to normal operations. | Solid Structures / Benign Materials, vessel activity similar to normal operations. | Solid Structures / Benign Materials, vessel activity similar to normal operations. | Solid Structures / Benign Materials, multiple vessels likely to be involved in removal. |
| | | Mattresses | Solid Structures / Benign Materials, vessel activity similar to normal operations. | Solid Structures / Benign Materials, vessel activity similar to normal operations. | Not Applicable - DECC guidance is for removal of mattresses. | Solid Structures / Benign Materials, multiple vessels likely to be involved in removal. |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Multiple vessels likely to be involved in removal. | Not Applicable - DECC guidelines require large structures to be recovered | Multiple vessels likely to be involved in removal. Increased risk of loss of well containment from dropped object during recovery operations. |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |
| | Noise Underwater and Onshore | Grout bags | No increase anticipated | No increase anticipated | No increase anticipated | No activity leading to noise above existing baseline offshore, some increase in noise associated with recycling (crushing) |
| | | Mattresses | No increase anticipated | No increase anticipated | Not Applicable - DECC guidance is for removal of mattresses. | No activity leading to noise above existing baseline offshore, some increase in noise associated with recycling (crushing) |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | No increase anticipated | Not Applicable - DECC guidelines require large structures to be recovered | No activity leading to noise above existing baseline offshore, some increase onshore associated with dismantling activity. |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |

6.4.4 Societal Impact

| Assessment Criteria | Aspects | OTHER STRUCTURES | | | | |
|---------------------|--|--|--|--|--|---|
| | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE | |
| SOCIETAL | Fisheries Impact | Outline Description | | | | |
| | | Grout bags | No change to current operations | Increase infrastructure on seabed, but in existing corridors / over trawlable. | Increase infrastructure on seabed, but in existing corridors. | No impact as grout bags occur in existing corridors / exclusions zones, so no additional fishing area available as a result of their removal. |
| | | Mattresses | No change to current operations | Increase infrastructure on seabed, but in existing corridors / over trawlable. | Not Applicable - DECC guidance is for removal of mattresses. | No impact as grout bags occur in existing corridors / exclusions zones, so no additional fishing area available as a result of their removal. |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Leaving redundant large structures on seabed, but in existing corridors / exclusions zones. | Not Applicable - DECC guidelines require large structures to be recovered | No impact as structure is in existing corridors / exclusions zones, so no additional fishing area available as a result of their removal. |
| | Community Disturbance - impacts onshore. | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |
| | | Grout bags | No incremental increase in waste coming onshore (only shipboard waste) | No incremental increase in waste coming onshore (only shipboard waste) | No incremental increase in waste coming onshore (only shipboard waste) | Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site |
| | | Mattresses | No incremental increase in waste coming onshore (only shipboard waste) | No incremental increase in waste coming onshore (only shipboard waste) | Not Applicable - DECC guidance is for removal of mattresses. | Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | No incremental increase in waste coming onshore (only shipboard waste) | Not Applicable - DECC guidelines require large structures to be recovered | Movements of waste onshore and noise associated with deconstruction. However, will use licensed onshore site |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |
| | | Waste Management | Grout bags | No new jobs will result from this option | No new jobs will result from this option | No new jobs will result from this option |
| | Mattresses | | No new jobs will result from this option | No new jobs will result from this option | Not Applicable - DECC guidance is for removal of mattresses. | Potential benefit is marginal due to quantity of structures recovered |
| | Frames pump skids, initially installed for PWRI, never commissioned. | | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | No new jobs will result from this option | Not Applicable - DECC guidelines require large structures to be recovered | Potential benefit is marginal due to quantity of structures recovered |
| | 2 anode skids | | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |
| | Workforce Welfare & Local Employment | Grout bags | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. | Potential for some negative stakeholder reaction to insitu decommissioning | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. |
| | | Mattresses | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. | Potential for some negative stakeholder reaction to insitu decommissioning | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Potential for some negative stakeholder reaction to long term in field suspension | Not Applicable - DECC guidelines require large structures to be recovered | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |

| Assessment Criteria | Aspects | | OTHER STRUCTURES | | | |
|----------------------|----------------------|--|--|--|--|--|
| | Outline Description | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| SOCIETAL (Continued) | Stakeholder Reaction | Grout bags | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. |
| | | Mattresses | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. | Potential for some negative stakeholder reaction to insitu decommissioning | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Potential for some negative stakeholder reaction to long term in field suspension | Not applicable - DECC guidelines require large structures to be recovered | Minimal reaction from stakeholders anticipated, general acceptance of decommissioning programme at stakeholder engagement. |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |

6

6.4.5 Economic

| Assessment Criteria | Aspects | | OTHER STRUCTURES | | | |
|---------------------|---------------------|--|---|--|--|---|
| | Outline Description | | RE-USE AT QUAD204 START-UP | SUSPEND LONG TERM | DECOMMISSION INSITU | RECOVER AND RECYCLE |
| ECONOMIC | Cost | Grout bags | Low relative cost | Low relative cost | Low relative cost | Moderate relative cost |
| | | Mattresses | Low relative cost | Low relative cost | Low relative cost | Moderate relative cost |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | Low relative cost | Not applicable - DECC guidelines require large structures to be recovered | Moderate relative cost |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |
| | Uncertainties | Grout bags | No uncertainties | No uncertainties | No uncertainties | Ability to recover due to integrity of grout bags - may collapse when moved |
| | | Mattresses | No uncertainties | No uncertainties | No uncertainties | Ability to recover due to integrity of mattresses - may collapse when moved |
| | | Frames pump skids, initially installed for PWRI, never commissioned. | Not Applicable - No functionality for Quad204 use and not connected to Schiehallion systems. No potential reuse. | No uncertainties | Not applicable - DECC guidelines require large structures to be recovered | Extent of existing damage to the frames may preclude recovery |
| | | 2 anode skids | Not Applicable - Redundant equipment near to the risers. No functionality for Quad204. | Not Applicable - Potentially would impede new riser terminations installation low | Not Applicable - classed as debris | Only technically feasible option. Would expect them to be recovered at same time as risers |

6

7.0 APPENDIX B – FIELD INFRASTRUCTURE DETAILS

7.1 OIL PRODUCTION STRUCTURES - Returned to Service at Quad 204 Start-Up

7.1.1 OIL Production Jumpers

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|------------|-------------------------|-------------|--|---|--------------------------------|
| PL1778/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 23 | In Service | Isolated at XT & M1A then flushed locally with glycol / potable water | Return to Service |
| PL1779/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 23 | In Service | Isolated at XT & M1A then flushed locally with glycol / potable water | Return to Service |
| PL1389/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 47 | In Service | Isolated at M1A & M1 then flushed locally with glycol / potable water | Return to Service |
| PL1775/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 25 | In Service | Isolated at XT & M1B then flushed locally with glycol / potable water | Return to Service |
| PL1393/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 72 | In Service | Isolated at M1B, & M1 then flushed locally with glycol / potable water | Return to Service |
| PL1394JCP0 8/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 26 | In Service | Isolated at XT & M1F then flushed locally with glycol / potable water | Return to Service |
| PL1394JCP2 2/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 25 | In Service | Isolated at XT & M1F then flushed locally with glycol / potable water | Return to Service |
| PL1394/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 45 | In Service | Isolated at M1F & M1 then flushed locally with glycol / potable water | Return to Service |
| PL2415 | Central | Jumper (Bundle) | Production | 6x6x2 | 52 | In Service | Isolated at XT CP04, CP23 & M1 then flushed locally with glycol / potable water | Return to Service |
| PL2419 | Central | Jumper (Bundle) | Production | 6x6x2 | 100 | In Service | Isolated at XT CP04, CP23 & M1 then flushed locally with glycol / potable water | Return to Service |
| PL1392/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 22 | In Service | Isolated at XT CP05, & M1 then flushed locally with glycol / potable water | Return to Service |
| PL1395/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 26 | In Service | Isolated at XT CP09, & M1 then flushed locally with glycol / potable water | Return to Service |
| PL1417/1-3 | West | Jumper (Bundle) | Production | 6x6x2 | 24 | In Service | Isolated at XT then flushed locally with glycol / potable water | Return to Service |
| PL1419/1-3 | West | Jumper (Bundle) | Production | 6x6x2 | 27 | In Service | Isolated at XT then flushed locally with glycol / potable water | Return to Service |
| PL1418/1-3 | West | Jumper (Bundle) | Production | 6x6x2 | 53 | In Service | Isolated at XT then flushed locally with glycol / potable water | Return to Service |
| PL1714/1-3 | West | Jumper (Bundle) | Production | 6x6x2 | 46 | In Service | Isolated at M24 & M21 then flushed locally with glycol / potable water | Return to Service |
| PL2021JWP 07/1-3 | West | Jumper (Bundle) | Production | 6x6x2 | 45 | In Service | Isolated at XT then flushed locally with glycol / potable water | Return to Service |
| PL2022JWP 13/1-3 | West | Jumper (Bundle) | Production | 6x6x2 | 38 | In Service | Isolated at XT then flushed locally with glycol / potable water | Return to Service |
| PL1362/1-3 | Loyal | Jumper (Bundle) | Production | 6x6x2 | 25 | In Service | Isolated at XT then flushed locally with glycol / potable water | Return to Service |
| PL1363/1-3 | Loyal | Jumper (Bundle) | Production | 6x6x2 | 25 | In Service | Isolated at XT then flushed locally with glycol / potable water | Return to Service |
| PL1364/1-3 | Loyal | Jumper (Bundle) | Production | 6x6x2 | 50 | In Service | Flush, isolate at M43 and M1 then recover and cross over test and prod and redeploy | Return to Service |
| PL1361R | Loyal | Jumper (Bundle) | Production | 8 | 55 | In Service | Flushed, pigged and suspended then relocated from F42 to M44 | Return to Service |
| PL2016.1-3(JLP03) | Loyal | Jumper (Bundle) | Production | 6x6x2 | 62 | In Service | Isolated at XT then flushed locally with glycol / potable water | Return to Service |
| PL2250 | NWAD | Jumper (Bundle) | Production | 6x6x2 | 114 | In Service | Isolated at XT then flushed locally with glycol / potable water | Return to Service |
| | | Total No | 70 | Total Length (m) | 3040 | Bundles have 3 Jumpers 2x Oil + 1x Gas in each bundle | | |

7.2 OIL Flowline Jumpers - to be suspended, but not recovered within Phase 1 Decomm window (recovery post 2015)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|------------|-------------------------|------------|--|--|--------------------------------|
| PL1774/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 23 | In Service | Isolated at XT & M1B then flushed locally with glycol / potable water | Brought onshore 2021 |
| PL2017.1-3(JLP07) | Loyal | Jumper (Bundle) | Production | 6x6x2 | 61 | In Service | Isolated at XT LP07 & M43 then flushed locally with glycol / potable water | Brought onshore 2018 |
| | | Total No | 6 | Total Length (m) | 252 | Bundles have 3 Jumpers 2x Oil + 1x Gas in each bundle | | |

7.3 CONTROL STRUCTURES - Returning to Service after Quad 204 Start-Up

7.3.1 CONTROL Fly to Place Connector (FTP)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------|----------|-----------------------|------------|----------------|---|--------------------------------|
| X | North | FTP | Controls | n/a | 112 | In Service | Isolate & Suspend | Return to Service |
| X | North | FTP | Controls | n/a | 79 | In Service | Relocated from UET U50 to CDA C30 in 2014 | Return to Service |
| X | North | FTP | Controls | n/a | 76 | In Service | Relocated from XT NW01 to CDA C29 in 2014 | Return to Service |
| X | FPSO | FTP | Controls | n/a | 49 | In Service | Relocated from DUTA D3 to DUTA D30 in 2015 (Parked 2013 - Hooked up 2015) | Return to Service |
| X | Loyal | FTP | Controls | n/a | 68 | In Service | Relocated from XT LW04A to CDA C31 in 2014 | Return to Service |
| PL1429 | West | FTP | Controls | n/a | 110 | In Service | Relocated from C21 to C21R (Parked 2013 - Hooked up 2014) | Return to Service |
| PL1430 | West | FTP | Controls | n/a | 80 | In Service | Relocated from C21 to C21R (Parked 2013 - Hooked up 2014) | Return to Service |
| PL1428 | West | FTP | Controls | n/a | 48 | In Service | Relocated from C21 to C21R (Parked 2013 - Hooked up 2014) | Return to Service |
| PL2024JWP 07/1-11 | West | FTP | Controls | n/a | 130 | In Service | Relocated from WP13 to C21R in 2014 | Return to Service |
| PL1715.1-13JWP13 | West | FTP | Controls | n/a | 92 | In Service | Relocated from C21 to C21R (Parked 2013 - Hooked up 2014) | Return to Service |
| PLU2175 | West | FTP | Controls | n/a | 114 | In Service | Relocated from C21 to C21R (Parked 2013 - Hooked up 2014) | Return to Service |
| PL1780/1-3 | Central | FTP | Controls | n/a | 60 | Out of service | REMOVED 2012?? Relocated from C1A to C35 in 2014 | Return to Service |
| PLU1406JC P03/1-3 | Central | FTP | Controls | n/a | 61 | In Service | Relocated from C1D to C35 in 2014 (Parked 2013 - Hooked up 2014) | Return to Service |
| PL1781/1-3 | Central | FTP | Controls | n/a | 70 | In Service | Relocated from C1A to C35 in 2014 | Return to Service |
| PL1408/1-3 | Central | FTP | Controls | n/a | 60 | Out of service | REMOVED 2012?? Relocated from C1P to C35 in 2014 | Return to Service |
| PL1407/1-3 | Central | FTP | Controls | n/a | 39 | In Service | Relocated from C1P to C1PR in 2014 | Return to Service |
| PL1411/1-3 | Central | FTP | Controls | n/a | 60 | In Service | Relocated from C1P to C1PR in 2014 | Return to Service |
| PLU1410JC P08/1-3 | Central | FTP | Controls | n/a | 94 | In Service | Relocated from C1P to C1PR in 2014 | Return to Service |
| XX | Central | FTP | Controls | n/a | 9 | In Service | Relocated from C1P to C1PR in 2014 | Return to Service |
| PL1777/1-3 | Central | FTP | Controls | n/a | 42 | In Service | Relocated from C1B to C36 in 2014 | Return to Service |
| PLU2283 | Central | FTP | Controls | n/a | 68 | In Service | Flush, preserve & suspend | Return to Service |
| XX | Central | FTP | Controls | n/a | 64 | In Service | Isolate & suspend | Return to Service |
| XX | Central | FTP | Controls | n/a | 84 | In Service | Isolate & suspend | Return to Service |
| XX | Central | FTP | Controls | n/a | 70 | In Service | Isolate & suspend | Return to Service |
| XX | Central | FTP | Controls | n/a | 94 | In Service | Isolate & suspend | Return to Service |
| XX | Central | FTP | Controls | n/a | TBD | In Service | Isolate & suspend | Return to Service |
| XX | Central | FTP | Controls | n/a | TBD | In Service | Isolate & suspend | Return to Service |
| XX | Loyal | FTP | Controls | n/a | 56 | In Service | Isolate & suspend | Return to Service |
| XX | Loyal | FTP | Controls | n/a | 56 | In Service | Isolate & suspend | Return to Service |
| XX | Loyal | FTP | Controls | n/a | 74 | In Service | Isolate & suspend | Return to Service |
| PLU2060 | Loyal | COCOT FTP | Controls | n/a | 91 | In Service | Isolate & suspend | Return to Service |
| PLU2061 | Loyal | COCOT FTP | Controls | n/a | 30 | In Service | Isolate & suspend | Return to Service |
| PLU2244 | FPSO for NWAD | FTP | Controls | n/a | TBD | In Service | Flush, preserve, disconnect and wet store for D30 hook-up in 2015 | Return to service |
| PLU2244 | NWAD | FTP | Controls | n/a | TBD | In Service | Isolate & suspend | Return to Service |
| PLU2549 | NWAD | FTP | Controls | n/a | 152 | In Service | Isolate & suspend | Return to Service |
| PLU2176 | West | FTP | Controls | n/a | 54 | In Service | Flush, preserve, disconnect and wet store for C25 hook-up | Return to Service |
| PLU2177 | West | FTP | Controls | n/a | 52 | In Service | Flush, preserve & suspend | Return to Service |
| PLU2178 | West | COCOT FTP | Controls | n/a | 81 | In Service | Isolate & suspend | Return to Service |

CONTROL Fly to Place Connector (FTP) continued

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|-----------|-------------------------|-------------|----------------|----------------------------|--------------------------------|
| PLU2179 | West | COCOT FTP | Controls | n/a | 81 | In Service | Isolate & suspend | Return to Service |
| PLU2180 | West | COCOT FTP | Controls | n/a | 43 | In Service | Isolate & suspend | Return to Service |
| PLU2181 | West | COCOT FTP | Controls | n/a | 108 | In Service | Isolate & suspend | Return to Service |
| PLU2182 | West | MARS FTP | Controls | n/a | 50 | In Service | Isolate & suspend (MARS??) | Return to Service |
| PLU2243 | West | FTP | Controls | n/a | TBD | In Service | Isolate & suspend | Return to Service |
| XX | West | FTP | Controls | n/a | 40 | In Service | Isolate & suspend | Return to Service |
| XX | West | FTP | Controls | n/a | 74 | In Service | Isolate & suspend | Return to Service |
| XX | West | FTP | Controls | n/a | 53 | In Service | Isolate & suspend | Return to Service |
| XX | West | FTP | Controls | n/a | 70 | In Service | Isolate & suspend | Return to Service |
| PLU2673 | West | MARS FTP | Controls | n/a | 20 | In Service | Isolate & suspend (MARS??) | Return to Service |
| PLU2981 | Central | FTP | Controls | n/a | 93 | In Service | Isolate & suspend | Return to Service |
| PLU2982 | Central | FTP | Controls | n/a | 93 | In Service | Isolate & suspend | Return to Service |
| PLU2935 | Loyal | FTP | Controls | n/a | 60 | In Service | Isolate & suspend | Return to Service |
| | | Total No | 51 | Total Length (m) | 3264 | | | |

7.3.2 Controls Distribution Assembly (CDA):

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|----------|-------------------------|------------|----------------|-------------------------|--------------------------------|
| XX | Central | CDA | Controls | n/a | n/a | In Service | Flushed & suspend | Return to Service |
| XX | Central | CDA | Controls | n/a | n/a | In Service | Flushed & suspend | Return to Service |
| XX | Central | CDA | Controls | n/a | n/a | In Service | Suspend | Return to Service |
| XX | Central | CDA | Controls | n/a | n/a | In Service | Isolate & Suspend | Return to Service |
| | | Total No | 4 | Total Length (m) | n/a | | | |

7.4 GAS SYSTEM STRUCTURES Returning to Service after Quad 204 Start-Up

7.4.1 GAS Flowlines

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|---------------------|-------------------------|--------------|----------------|---|--------------------------------|
| PL1396 | Central | Flowline | Gas Lift | 8 | 2872 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL1759 | Foinaven | Flowline | Gas Import / Export | 10 | 6767 | In service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | In Service |
| PL1760 | Sullom Voe | Flowline | Gas Import / Export | 12 | 16803 | In service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | In Service |
| PL2167 | Central | Flowline | Gas Import / Export | 8 | 2628 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL1365 | Loyal | Flowline | Gas Lift | 6 | 5979 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL2248 | NWAD | Flowline | Gas Lift | 8 | 3041 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL1420 | West | Flowline | Gas lift | 6 | 3270 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| | | Total No | 7 | Total Length (m) | 41360 | | | |

7.4.2 GAS Flowline Termination Assemblies (FTAs)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|---------------------|-------------------------|------------|----------------|---|--------------------------------|
| PL1396 | Central | FTA | Gas Lift | 8 | 5 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL1420 | FPSO for Central | FTA | Gas Lift | 8 | 5 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL1420 | West | FTA | Gas Lift | 6 | 5 | In Service | Isolated at FTA F25, M21, F35 & flushed locally with glycol / water | Return to service |
| PL1420 | FPSO for West | FTA | Gas Lift | 6 | 5 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL1365 | Loyal | FTA | Gas Lift | 6 | 5 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL1365 | FPSO for Loyal | FTA | Gas Lift | 6 | 5 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL1760 | Central | FTA | Gas Export | 10 | 5 | In Service | Isolated at M1J manifold and M1C & flushed locally with glycol / water | In Service |
| PL2167 | FPSO for GE | FTA | Gas Import / Export | 8 | 5 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL2167 | Central | FTA | Gas Import / Export | 8 | 5 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL2248 | NWAD | FTA | Gas Lift | 8 | 5 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL2248 | FPSO for NWAD | FTA | Gas Lift | 8 | 5 | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| XX | Central | FTA | Gas Export | n/a | n/a | In Service | Isolated at M1J manifold and M1C & flushed locally with glycol / water | In Service |
| XX | Foinaven | FTA | Gas Export | n/a | n/a | In Service | In Service | In Service |
| | | Total No | 13 | Total Length (m) | 55 | | | |

7.4.3 Gas Jumpers

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|-----------|-------------------------|-------------|----------------|--|--------------------------------|
| PL1759 | Central | Gas Jumper | Gas | 8 | 78 | In Service | Isolated at M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| PL1760 | Central | Gas Jumper | Gas | 8 | 75 | In Service | Isolated at M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| PL2842JM1J | Central | Gas Jumper | Gas | 8 | 65 | In Service | Isolated at M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| PL1849 | Central | Gas Jumper | Gas | 8 | 94 | In Service | Isolated at M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| PL1396 | Central | Gas Jumper | Gas | 8 | 107 | In Service | Isolated at M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| PL2167J2 | Central | Gas Jumper | Gas | 6 | 360 | In Service | Isolated at M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| PL2843JM8 | Central | Gas Jumper | Gas | 8 | 35 | In Service | Isolated at M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| PL1420 | West | Gas Jumper | Gas | 6 | 72 | In Service | Isolated at M25,M21 & F25, flushed & then disconnect and hook up from M21 to M25 | Return to Service |
| PL1365 | Loyal | Gas Jumper | Gas | 6 | 87 | In Service | Isolated at XT's,M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| PL2248 | NWAD | Gas Jumper | Gas | 8 | 69 | In Service | Isolated at XT's,M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| PL1420 | FPSO to GL | Gas Jumper | Gas | 6 | 104 | In Service | Isolated at XT's,M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| XX | FPSO to Loyal | Gas Jumper | Gas | 6 | 114 | In Service | Isolated at XT's,M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| PL2248 | FPSO to GL | Gas Jumper | Gas | 6 | 275 | In Service | Isolated at XT's, M31, F11 , M1J & M1C & then disconnect and hook up from F131 to M32 | Return to service |
| PL2167J1 | FPSO to GI / GE | Gas Jumper | Gas | 6 | 90 | In Service | Isolated at M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| PL1431 | FPSO to Disposal | Gas Jumper | Gas | 8 | 41 | In Service | Isolated at M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to Service |
| | | Total No | 15 | Total Length (m) | 1666 | | | |

7.4.4 GAS Manifolds

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|----------------------------|-------------------------|------------|----------------|---|--------------------------------|
| PL1849 | Central | Manifold | Gas Import / Export / Lift | n/a | n/a | In Service | Isolated at XT's, M31, F31 & F21 then flushed locally with glycol / potable water | Return to service |
| PL2843M8 | Central | Manifold | Gas Import / Export | n/a | n/a | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| XX | Central | Manifold | Gas Import / Export | n/a | n/a | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| PL1431 | FPSO | Manifold | Gas Import / Export | n/a | n/a | In Service | Isolated at XT's, M31, F11 , M1J & M1C then flushed locally with glycol / potable water | Return to service |
| | | Total No | 4 | Total Length (m) | n/a | | | |

7.4.5 GAS Pipeline End Manifold

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|------|------------|-----------------------|------------|----------------|-------------------------|--------------------------------|
| XX | Foinaven | PLEM | Gas Export | n/a | n/a | In Service | In Service | In Service |

7.5 WATER INJECTION STRUCTURES - Returning to Service after Quad 204 Start-Up

7.5.1 WI Flowlines

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|-----------------|-------------------------|--------------|----------------|---|--------------------------------|
| PL1397 | Central | Flowline | Water Injection | 12 | 2548 | In Service | Flushed with filtered inhibited seawater & then isolated at XT's,F71, F16 & F38 | Return to service |
| PL1366 | Loyal | Flowline | Water Injection | 10 | 4883 | In Service | Flushed with filtered inhibited seawater & then isolated at XT's,F71, F16 & F38 | Return to service |
| PL1412 | North | Flowline | Water Injection | 10 | 2271 | In Service | Flushed with filtered inhibited seawater & then isolated at XT's,F71, F16 & F38 | Return to service |
| PL2247 | NWAD | Flowline | Water Injection | 12 | 3141 | In Service | Flushed with filtered inhibited seawater & then isolated at XT's,F71, F16 & F38 | Return to service |
| PL1421 | West | Flowline | Water Injection | 10 | 3507 | In Service | Flushed with filtered inhibited seawater & then isolated at XT's,F71, F16 & F38 | Return to service |
| PL1982 | West | Flowline | Water Injection | 12 | 2840 | In Service | Flushed with filtered inhibited seawater & then isolated at XT's,F71, F16 & F38 | Return to service |
| | | Total No | 6 | Total Length (m) | 19190 | | | |

7.5.2 WI Flowline Termination Assembly (FTA)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|-----------------|-------------------------|------------|----------------|--|--------------------------------|
| PL1397 | Central | FTA | Water Injection | 10 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1397 | FPSO for Central | FTA | Water Injection | 10 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1421 | West | FTA | Water Injection | 10 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1421 | FPSO for West | FTA | Water Injection | 10 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1982 | West | FTA | Water Injection | 8 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1982 | FPSO for West | FTA | Water Injection | 10 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1366 | Loyal | FTA | Water Injection | 10 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1412 | North | FTA | Water Injection | 10 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1366 | North | FTA | Water Injection | 10 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1412 | FPSO for North | FTA | Water Injection | 10 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL2247 | NWAD | FTA | Water Injection | 10 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL2247 | FPSO for NWAD | FTA | Water Injection | 10 | 5 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| | | Total No | 12 | Total Length (m) | 60 | | | |

7.5.3 WI Jumper

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|------------------|-----------------|-----------------------|------------|----------------|--|--------------------------------|
| PL1397J CW17 | Central | Water Inj Jumper | Water Injection | 6 | 29 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1397J CW18 | Central | Water Inj Jumper | Water Injection | 6 | 37 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1397J CW19 | Central | Water Inj Jumper | Water Injection | 6 | 28 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1397J CW15 | Central | Water Inj Jumper | Water Injection | 6 | 52 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1397 | Central | Water Inj Jumper | Water Injection | 10 | 45 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1398 | Central | Water Inj Jumper | Water Injection | 6 | 31 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1399 | Central | Water Inj Jumper | Water Injection | 6 | 44 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1401 | Central | Water Inj Jumper | Water Injection | 6 | 24 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1400 | Central | Water Inj Jumper | Water Injection | 6 | 35 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1397 | Central | Water Inj Jumper | Water Injection | 10 | 83 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |

WI Jumper continued

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|------------------|-----------------|-------------------------|-------------|----------------|--|--------------------------------|
| PL1421J WW08 | West | Water Inj Jumper | Water Injection | 6 | 25 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1421J WW09 | West | Water Inj Jumper | Water Injection | 6 | 21 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1421J WW10 | West | Water Inj Jumper | Water Injection | 6 | 58 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL2023J WW11 | West | Water Inj Jumper | Water Injection | 6 | 42 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL2414 | West | Water Inj Jumper | Water Injection | 6 | 26 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL2174 | West | Water Inj Jumper | Water Injection | 6 | 35 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1982 | West | Water Inj Jumper | Water Injection | 12 | 67 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1421 | West | Water Inj Jumper | Water Injection | 10 | 48 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1422 | West | Water Inj Jumper | Water Injection | 6 | 34 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1423 | West | Water Inj Jumper | Water Injection | 6 | 23 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1424 | West | Water Inj Jumper | Water Injection | 6 | 28 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1421 | West | Water Inj Jumper | Water Injection | 10 | 38 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1368/1 -3 | Loyal | Water Inj Jumper | Water Injection | 6 | 48 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1367/1 -3 | Loyal | Water Inj Jumper | Water Injection | 6 | 36 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1369/1 -3 | Loyal | Water Inj Jumper | Water Injection | 6 | 32 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1366 | Loyal | Water Inj Jumper | Water Injection | 10 | 52 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL2251 | NWAD | Water Inj Jumper | Water Injection | 6 | 36 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL2252 | NWAD | Water Inj Jumper | Water Injection | 6 | 38 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL2247 | NWAD | Water Inj Jumper | Water Injection | 10 | 59 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1713 | North | Water Inj Jumper | Water Injection | 6 | 35 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1413 | North | Water Inj Jumper | Water Injection | 6 | 28 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1412 | North | Water Inj Jumper | Water Injection | 10 | 55 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1366 | North | Water Inj Jumper | Water Injection | 10 | 48 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL1982 | FPSO to West | Water Inj Jumper | Water Injection | 10 | 244 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| PL2247 | FPSO to NWAD | Water Inj Jumper | Water Injection | 10 | 255 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to Service |
| | | Total No | 35 | Total Length (m) | 1819 | | | |

7.5.4 WI Manifold

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|-----------------|-------------------------|------------|----------------|--|--------------------------------|
| PL1397 | Central | Manifold | Water Injection | n/a | n/a | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1397 | Central | Manifold | Water Injection | n/a | n/a | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1421 | West | Manifold | Water Injection | n/a | n/a | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1421 | West | Manifold | Water Injection | n/a | n/a | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1366 | Loyal | Manifold | Water Injection | n/a | n/a | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL1412 | North | Manifold | Water Injection | n/a | n/a | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL2247 | FPSO | Manifold | Water Injection | n/a | n/a | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| PL2247 | NWAD | Manifold | Water Injection | n/a | n/a | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Return to service |
| | | Total No | 8 | Total Length (m) | n/a | | | |

7.6 WI Flowline Jumper to be suspended, but not recovered within Phase 1 Decomm window (recovery post 2015)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|------------------|-----------------|-----------------------|------------|----------------|--|--------------------------------|
| PL1414 | North | Water Inj Jumper | Water Injection | 6 | 34 | In Service | Isolated at XT NW02 & M61 then flushed locally with glycol / potable water | Brought onshore 2018 |

7.7 OIL PRODUCTION STRUCTURES – LONG TERM SUSPENSION

7.7.1 OIL Flowlines

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|------------|-------------------------|--------------|----------------|---|--------------------------------|
| PL1384 | Central | Flowline | Production | 10 | 2550 | In Service | Flushed, Piggged, Treated and Suspended | Suspended & Monitor |
| PL1385 | Central | Flowline | Production | 10 | 2554 | In Service | Flushed, Piggged, Treated and Suspended | Suspended & Monitor |
| PL1386 | Central | Flowline | Production | 10 | 2530 | In Service | Flushed, Piggged, Treated and Suspended | Suspended & Monitor |
| PL1387 | Central | Flowline | Production | 8 | 2579 | In Service | Flushed, Piggged, Treated and Suspended | Suspended & Monitor |
| PL1361 | Loyal | Flowline | Production | 8 | 5795 | In Service | Flushed, Piggged, Treated and Suspended | Suspended & Monitor |
| PL1360 | Loyal | Flowline | Production | 10 | 5755 | In Service | Flushed, Piggged, Treated and Suspended | Suspended & Monitor |
| PL2245 | NWAD | Flowline | Production | 10 | 2820 | In Service | Flushed, Piggged, Treated and Suspended | Suspended & Monitor |
| PL1415 | West | Flowline | Production | 8 | 2867 | In Service | Flushed, Piggged, Treated and Suspended | Suspended & Monitor |
| PL1416 | West | Flowline | Production | 10 | 2822 | In Service | Flushed, Piggged, Treated and Suspended | Suspended & Monitor |
| PL2141 | West | Flowline | Production | 10 | 2507 | In Service | Flushed, Piggged, Treated and Suspended | Suspended & Monitor |
| | | Total No | 10 | Total Length (m) | 32779 | | | |

7.7.2 OIL Flowline Termination Assemblies (FTA's)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|------------|-------------------------|------------|----------------|--|--------------------------------|
| PL1387 | Central | FTA | Production | 8 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1385 | Central | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1387 | FPSO for Central | FTA | Production | 8 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1385 | FPSO for Central | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1384 | Central | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1386 | Central | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1384 | FPSO for Central | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1386 | FPSO for Central | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1415 | West | FTA | Production | 8 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1416 | West | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1415 | FPSO for West | FTA | Production | 8 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1416 | FPSO for West | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL2141 | West | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL2141 | FPSO for West | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1361 | Loyal | FTA | Production | 8 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1361 | Loyal | FTA | Production | 8 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1360 | Loyal | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL1360 | Loyal | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL2245 | NWAD | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| PL2245 | FPSO for NWAD | FTA | Production | 10 | 5 | In Service | Flushed, Pigged, Treated and Suspended | Suspended & Monitor |
| | | Total No | 20 | Total Length (m) | 100 | | | |

7.7.3 OIL Manifold

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|----------|-----------------|-----------------------|------------|----------------|--|--------------------------------|
| XX | Central | Manifold | Production & GL | n/a | n/a | In Service | Isolated at XTs & M1D, flushed locally with glycol / potable water and suspended | Suspended & Monitor |

7.8 CONTROL STRUCTURES – LONG TERM SUSPENSION

7.8.1 CONTROL Static Umbilical

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|------------------|-----------|-------------------------|--------------|----------------|---------------------------|--------------------------------|
| PLU2242 | Central | Static Umbilical | Controls | 10 | 4750 | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1402/1-5 | Central | Static Umbilical | Controls | 10 | 2800 | Suspended | Suspended & Monitor | Suspended & Monitor |
| PL1379/1-7 | FPSO | Static Umbilical | Controls | 10 | 250 | Suspended | Suspended & Monitor | Suspended & Monitor |
| PL1425/1-7 | FPSO | Static Umbilical | Controls | 10 | 200 | Suspended | Suspended & Monitor | Suspended & Monitor |
| PL1434/1-2 | Gas Disposal | Static Umbilical | Controls | 10 | 3679 | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1371/1-5 | Loyal | Static Umbilical | Controls | 10 | 4812 | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1383/1-5 | North | Static Umbilical | Controls | 10 | 2382 | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PLU2244 | NWAD | Static Umbilical | Controls | 10 | 3977 | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PLU2243 | West | Static Umbilical | Controls | 10 | 3441 | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1427/1-6 | West | Static Umbilical | Controls | 10 | 2986 | Suspended | Suspended & Monitor | Suspended & Monitor |
| | | Total No | 10 | Total Length (m) | 29277 | | | |

7.8.2 CONTROL Umbilical End Termination (UET)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|-----------|-------------------------|------------|----------------|---------------------------|--------------------------------|
| PLU2242 | Central | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1402/1-5 | Central | UET | Controls | n/a | n/a | Suspended | Suspended & Monitor | Suspended & Monitor |
| PL1379/1-7 | FPSO | UET | Controls | n/a | n/a | Suspended | Suspended & Monitor | Suspended & Monitor |
| PL1425/1-7 | FPSO | UET | Controls | n/a | n/a | Suspended | Suspended & Monitor | Suspended & Monitor |
| PL1434/1-2 | Gas Disposal | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1371/1-5 | Loyal | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1383/1-5 | North | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PLU2244 | FPSO for NWAD | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PLU2243 | FPSO for Gas Disposal | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1427/1-6 | West | UET | Controls | n/a | n/a | Suspended | Suspended & Monitor | Suspended & Monitor |
| PLU2242 | Central | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1402/1-5 | Central | UET | Controls | n/a | n/a | Suspended | Suspended & Monitor | Suspended & Monitor |
| PL1379/1-7 | FPSO | UET | Controls | n/a | n/a | Suspended | Suspended & Monitor | Suspended & Monitor |
| PL1425/1-7 | FPSO | UET | Controls | n/a | n/a | Suspended | Suspended & Monitor | Suspended & Monitor |
| PL1434/1-2 | Gas Disposal | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1371/1-5 | Loyal | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1383/1-5 | North | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PLU2244 | NWAD | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PL1427/1-6 | West | UET | Controls | n/a | n/a | Suspended | Suspended & Monitor | Suspended & Monitor |
| PL1434/1-2 | Gas Disposal | UET | Controls | n/a | n/a | In Service | Flush, preserve & suspend | Suspended & Monitor |
| | | Total No | 20 | Total Length (m) | n/a | | | |

7.8.3 CONTROLS Fly to Place connector (FTP)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|----------|-------------------------|------------|----------------|--|--------------------------------|
| PL1435/1-2 | Gas Disposal | FTP | Controls | n/a | 82 | In Service | Flush, preserve & suspend | Suspended & Monitor |
| PLU2258 | NWAD | FTP | Controls | n/a | 152 | Out of use | Out of use - within IPR (Brought onshore 2013????) | ??? |
| PL1426/1-6 | FPSO | FTP | Controls | 10 | 190 | Suspended | Suspended & Monitor | Suspended & Monitor |
| PLU1889 | FPSO | FTP | Controls | 10 | 255 | Suspended | Suspended & Monitor | Suspended & Monitor |
| | | Total No | 4 | Total Length (m) | 679 | | | |

7.9 GAS SYSTEM STRUCTURES – LONG TERM SUSPENSION

7.9.1 GAS Flowlines

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|----------|--------------|-----------------------|------------|----------------|---|--------------------------------|
| PL1431 | Gas Disposal | Flowline | Gas Disposal | 8 | 6613 | Suspended | Isolated at XT, M31, F31 & F21 then flushed locally with glycol / potable water | Suspended & Monitor |

7.9.2 GAS Flowline Termination Assemblies (FTAs)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|--------------|-------------------------|------------|----------------|---|--------------------------------|
| XX | Disposal | FTA | Gas Disposal | 8 | 5 | Suspended | Isolated at XT, M31, F31 & F21 then flushed locally with glycol / potable water | Suspended & Monitor |
| PL1431 | FPSO for Disposal | FTA | Gas Disposal | 8 | 5 | Suspended | Isolated at XT, M31, F31 & F21 then flushed locally with glycol / potable water | Suspended & Monitor |
| | | Total No | 2 | Total Length (m) | 10 | | | |

7.9.3 Gas Jumper

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|------------|--------------|-----------------------|------------|----------------|-------------------------------------|--------------------------------|
| PL1432 | Disposal | Gas Jumper | Gas Disposal | 8 | 45 | Suspended | Flush, Treat & Locally then Suspend | Suspended & Monitor |

7.10 WATER INJECTION SYSTEM STRUCTURES – LONG TERM SUSPENSION

No WI structures identified for long term suspension.

7.11 OIL PRODUCTION SYSTEM STRUCTURES – RECOVER AND RECYCLE

7.11.1 Oil Risers

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|------------|-------------------------|-------------|----------------|---|---------------------------------------|
| PL1384 | FPSO | Riser | Production | 10 | 733 | In Service | Flushed, Piggged & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL1385 | FPSO | Riser | Production | 10 | 741 | In Service | Flushed, Piggged & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL1386 | FPSO | Riser | Production | 10 | 738 | In Service | Flushed, Piggged & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL1387 | FPSO | Riser | Production | 8 | 732 | In Service | Flushed, Piggged & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL1904 | FPSO | Riser | Production | 10 | 725 | In Service | Flushed, Piggged & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL1361 | FPSO | Riser | Production | 8 | 750 | In Service | Flushed, Piggged & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL1360 | FPSO | Riser | Production | 10 | 777 | In Service | Flushed, Piggged & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL2245 | FPSO | Riser | Production | 10 | 705 | In Service | Flushed, Piggged & then Recovered after FPSO is off station | Condition at Quad 204 Start-Up |
| PL1415 | FPSO | Riser | Production | 8 | 734 | In Service | Flushed, Piggged & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL1416 | FPSO | Riser | Production | 10 | 773 | In Service | Flushed, Piggged & then Recovered after FPSO is off station | Brought onshore 2013 |
| | | Total No | 10 | Total Length (m) | 7408 | | | |

7.11.2 OIL Riser End Terminations (RET)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|------------|-------------------------|------------|----------------|--|--------------------------------|
| PL1904 | FPSO for West | RET | Production | 10 | 3 | In Service | Flushed, Treated, Abandoned & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL2245 | FPSO for NWAD | RET | Production | 10 | 3 | In Service | Flushed, Treated, Abandoned & then Recovered after FPSO is off station | Brought onshore 2013 |
| | | Total No | 2 | Total Length (m) | 6 | | | |

7.11.3 OIL Production Jumpers

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|------------|-----------------------|------------|----------------|---|--------------------------------|
| PL1390JCP0 3/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 45 | In Service | Isolated at XT CP20, CP03 & M1 then flushed locally with glycol / potable water | Brought onshore 2014 |
| PL1390JCP2 0/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 22 | In Service | Isolated at XT CP20, CP03 & M1 then flushed locally with glycol / potable water | Brought onshore 2014 |
| PL1390/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 50 | In Service | Isolated at M1D, & M1 then flushed locally with glycol / potable water | Brought onshore 2014 |

OIL Production Jumpers continued

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|------------|-------------------------|-------------|--|---|---------------------------------------|
| PL1388JCP0 1/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 35 | In Service | Isolated at XT CP21, CP01 & M1 then flushed locally with glycol / potable water | Brought onshore 2014 |
| PL1388/1-3 | Central | Jumper (Bundle) | Production | 6x6x2 | 116 | In Service | Isolated at XT CP21, CP01 & M1 then flushed locally with glycol / potable water | Brought onshore 2014 |
| PL1386 | Central | Prod Jumper | Production | 10 | 94 | In Service | Flushed, Pigged & Isolated at M1 | Brought onshore 2014 |
| PL1387 | Central | Prod Jumper | Production | 8 | 86 | In Service | Flushed, Pigged & Isolated at M1 | Brought onshore 2014 |
| PL1384 | Central | Prod Jumper | Production | 10 | 82 | In Service | Flushed, Pigged & Isolated at M1 | Brought onshore 2014 |
| PL1385 | Central | Prod Jumper | Production | 10 | 75 | In Service | Flushed, Pigged & Isolated at M1 | Brought onshore 2014 |
| PL1416 | West | Prod Jumper | Production | 10 | 47 | In Service | Flushed, Pigged & then Recovered | Condition at Quad 204 Start-Up |
| PL1415 | West | Prod Jumper | Production | 8 | 52 | In Service | Flushed, Pigged & then Recovered | Brought onshore 2013 |
| PL2173 | West | Jumper (Bundle) | Production | 6x6x2 | 34 | In Service | Flushed, Disconnected & then Recovered (fit FTC to flow base) | Brought onshore 2014 |
| PL2141 | West | Prod Jumper | Production | 10 | 285 | In Service | Flushed, Pigged & Suspended | Brought onshore 2014 |
| PL1360 | Loyal | Prod Jumper | Production | 10 | 44 | In Service | Flushed, Pigged & then Recovered | Brought onshore 2014 |
| PL2245 | NWAD | Prod Jumper | Production | 10 | 55 | In Service | Isolated at XTs & M121 then flushed locally with glycol / potable water | Brought onshore 2014 |
| PL2245 | FPSO to NWAD | Prod Jumper | Production | 10 | 99 | In Service | Flushed, Pigged & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL2245 | FPSO to NWAD | Prod Jumper | Production | 10 | 63 | In Service | Flushed, Pigged & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL2141 | FPSO to West | Prod Jumper | Production | 10 | 188 | In Service | Flushed, Pigged & then Recovered after FPSO is off station | Brought onshore 2013 |
| | | Total No | 30 | Total Length (m) | 2076 | Bundles have 3 Jumpers 2x Oil + 1x Gas in each bundle | | |

7.12 CONTROL SYSTEM STRUCTURES – RECOVER AND RECYCLE

7.12.1 CONTROL Dynamic Umbilical

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-------------------|----------|-------------------------|-------------|----------------|---|--------------------------------|
| PL1380/1-7 | FPSO | Dynamic Umbilical | Controls | 8 | 740 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2241 | FPSO | Dynamic Umbilical | Controls | 12 | 1924 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1375/1-7 | FPSO | Dynamic Umbilical | Controls | 8 | 725 | Suspended | Recover 2013 (sealed) | Brought onshore 2013 |
| | | Total No | 3 | Total Length (m) | 3389 | | | |

7.12.2 CONTROL Dynamic Umbilical Termination Assembly (DUTA)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|------|----------|-----------------------|------------|----------------|-------------------------|--------------------------------|
| PL1375 | FPSO | DUTA | Controls | n/a | n/a | Suspended | Recover 2013 (sealed) | Brought onshore 2013 |

7.12.3 CONTROL Fly to Place connector (FTP)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|------|----------|-----------------------|------------|----------------|---|--------------------------------|
| PL1403/1-5 | Central | FTP | Controls | n/a | 149 | Out of use | Out of use - within IPR (recover and brought onshore 2013) | Brought onshore 2013 |
| PL1403/1-5 | Central | FTP | Controls | n/a | 90 | Out of use | Out of use - within IPR (recover and brought onshore 2013) | Brought onshore 2013 |
| PL1403/1-5 | Central | FTP | Controls | n/a | TBD | Out of use | Out of use - within IPR (recover and brought onshore 2013) | Brought onshore 2013 |
| PL1404a/1-3 | Central | FTP | Controls | n/a | 90 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1405/1-3 | Central | FTP | Controls | n/a | 66 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1406/1-3 | Central | FTP | Controls | n/a | 66 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1409/1-3 | Central | FTP | Controls | n/a | 110 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1410/1-3 | Central | FTP | Controls | n/a | 82 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1776/1-3 | Central | FTP | Controls | n/a | 40 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1850.1-10 | Central | FTP | Controls | n/a | 98 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU1406JC P20/1-3 | Central | FTP | Controls | n/a | 31 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU1406JC P21/1-3 | Central | FTP | Controls | n/a | 60 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2242 | Central | FTP | Controls | n/a | TBD | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2260 | Central | FTP | Controls | n/a | 104 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |

CONTROL Fly to Place Connector (FTP) continued

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|------------|----------|-----------------------|------------|----------------|---|--------------------------------|
| PLU2261 | Central | FTP | Controls | n/a | 112 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2270 | Central | FTP | Controls | n/a | 145 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2283 | Central | FTP | Controls | n/a | 200 | In Service | Hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| XX | Central | FTP | Controls | n/a | 280 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| XX | Central | FTP | Controls | n/a | 70 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2283 | Central | FTP | Controls | n/a | TBD | Suspended | Hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2282 | Central | FTP | Controls | n/a | 164 | In Service | Hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2420 | Central | FTP | Controls | n/a | 60 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2734 | Central | FTP | Controls | n/a | 135 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2844 | Central | FTP | Controls | n/a | 146 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1382/1-5 | FPSO | FTP | Controls | n/a | 54 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1440 | FPSO | FTP | Controls | n/a | 90 | Out of use | Recover 2013 (sealed) | Brought onshore 2013 |
| PL1376/1-6 | FPSO | FTP | Controls | n/a | 40 | Out of use | Recover 2013 (sealed) | Brought onshore 2013 |
| PL1439 | FPSO | FTP | Controls | n/a | 60 | Out of use | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| XX | FPSO | FTP | Controls | n/a | TBD | Out of use | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1372/1-3 | Loyal | FTP | Controls | n/a | 130 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1373/1-3 | Loyal | FTP | Controls | n/a | 90 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1374/1-3 | Loyal | FTP | Controls | n/a | 88 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL2018.1-9(JLP07) | Loyal | FTP | Controls | n/a | 138 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL2019.1-6(JLW10) | Loyal | FTP | Controls | n/a | 120 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| XX | Loyal | FTP | Controls | n/a | 94 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2059 | Loyal | COCO T FTP | Controls | n/a | 125 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1370/1-5 | North | FTP | Controls | n/a | 89 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL2025JWW 11/1-13 | West | FTP | Controls | n/a | 166 | Out of use | Recovered or recovered in 2013??? | Brought onshore 2013 |
| PLU2183 | West | FTP | Controls | n/a | 78 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |

CONTROL Fly to Place Connector (FTP) continued

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|-----------|-------------------------|-------------|----------------|---|--------------------------------|
| PLU2243 | West | FTP | Controls | n/a | TBD | In Service | Recover 2013 (chemical cores flushed, hydraulic fluid left) | Brought onshore 2013 |
| PLU2278 | West | FTP | Controls | n/a | 90 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PLU2279 | West | FTP | Controls | n/a | 147 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1433 | West | FTP | Controls | n/a | 30 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| XX | West | FTP | Controls | n/a | 87 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| XX | West | FTP | Controls | n/a | 130 | In Service | Chemical cores flushed, hydraulic fluid left in situ and recovered 2013 | Brought onshore 2013 |
| PL1377/1-6 | FPSO | FTP | Controls | 10 | 170 | Suspended | Suspended & Recovered in 2015 | Brought onshore 2015 |
| PL1381/1-6 | FPSO | FTP | Controls | 10 | 145 | Suspended | Suspended & Recovered in 2013 | Brought onshore 2013 |
| PLU2934 | Loyal | FTP | Controls | n/a | 73 | Out of use | Recovered in 2013 | Brought onshore 2013 |
| | | Total No | 48 | Total Length (m) | 4532 | | | |

7.12.4 Controls Distribution Assembly (CDA):

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|----------|-------------------------|------------|----------------|-------------------------|--------------------------------|
| PLU2254 | NWAD | CDA | Controls | n/a | n/a | In Service | Flushed and preserved | Brought onshore 2014 |
| XX | West | CDA | Controls | n/a | n/a | In Service | Flushed and preserved | Brought onshore 2014 |
| | Central | CDA | Controls | n/a | n/a | In Service | Flushed and preserved | Brought onshore 2014 |
| XX | Central | CDA | Controls | n/a | n/a | In Service | Flushed & suspend | Brought onshore 2014 |
| | | Total No | 4 | Total Length (m) | n/a | | | |

7.13 GAS SYSTEM STRUCTURES – RECOVER AND RECYCLE

7.13.1 Gas Risers

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|---------------------|-------------------------|-------------|----------------|---|--------------------------------|
| PL1396 | FPSO | Riser | Gas Lift | 8 | 749 | In Service | Flushed, Treated & then Recovered after FPSO is off station | Brought onshore 2013 |
| PL1431 | FPSO | Riser | Gas Import / Export | 8 | 721 | In Service | Flushed, Treated & then Recovered after FPSO is off station | Brought onshore 2013 |
| | | Total No | 2 | Total Length (m) | 1470 | | | |

7.14 WATER INJECTION SYSTEM STRUCTURES – RECOVER AND RECYCLE

7.14.1 WI Riser

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|-----------------|-----------------|-------------------------|-------------|----------------|--|--------------------------------|
| PL1397 | FPSO | Riser | Water Injection | 10 | 697 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Brought onshore 2013 |
| PL1412 | FPSO | Riser | Water Injection | 12 | 777 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Brought onshore 2013 |
| PL1982 | FPSO | Riser | Water Injection | 12 | 725 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Brought onshore 2013 |
| | | Total No | 3 | Total Length (m) | 2199 | | | |

7.14.2 WI Riser End Termination (RET)

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|------|-----------------|-----------------------|------------|----------------|--|--------------------------------|
| PL1982 | FPSO for West | RET | Water Injection | 10 | 3 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Brought onshore 2013 |

7.14.3 WI Jumper

| DECC Pipeline Number | Field Location / Drill Centre | Type | Process | Nominal Diameter (in) | Length (m) | Current Status | Field Suspension Status | Condition at Quad 204 Start-Up |
|----------------------|-------------------------------|------------------|-----------------|-------------------------|------------|----------------|--|--------------------------------|
| PL2020 (JLW10) | Loyal | Water Inj Jumper | Water Injection | 6 | 82 | In Service | Flushed, Treated & then recovered in 2014 after setting M45 | Brought onshore 2014 |
| PL1982 | FPSO to West | Water Inj Jumper | Water Injection | 12 | 180 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Brought onshore 2013 |
| PL1421 | FPSO to North | Water Inj Jumper | Water Injection | 10 | 78 | In Service | Flushed with filtered inhibited seawater & then isolated at XTs,F71, F16 & F38 | Brought onshore 2013 |
| | | Total No | 3 | Total Length (m) | 340 | | | |